
813 N Franklin St

Tampa, Hillsborough County, FL 33602

REPORT **PLM-20261014151531**



Mapbox Satellite imagery (Maxar) at parcel zoom, north up, retrieved 14 Oct 2026. Subject point: the geocoded address (parcel lines not drawn). Geocode: US Census Geocoder, exact match (TIGER line 104530091).

OVERALL RATING · FIVE-STEP SCALE

Moderate 2.3 of 10

RECOMMENDATION

Some factors warrant attention; enhanced due diligence before acquisition. Next steps before closing: the insurer's sinkhole coverage, given the carbonate rock; a PFAS tap-water or well test, which is how to know, or the utility's PFAS results.

FINDINGS THAT WARRANT FOLLOW-UP

2 High of 16 sections; the last column says where. All 16 on page 3.

06	Soil and geology	High	Carbonate rock, karst-prone (limestone, Tampa Member)	§ 04
13	PFAS	High	Peter O Knight 2.5 mi: potential PFAS source, not measured	§ 08

Low	**Moderate**	Elevated	High	Severe
composite below 2.1	composite 2.1 to 4.0 ◂ THIS PROPERTY	composite 4.1 to 6.5	composite 6.6 and above	trigger: Superfund NPL site within 0.5 mi

Checks: passed. Every core source answered, every figure reconciled to its record, every cross-check passed; this is a retrieval and consistency check, not a verification of the underlying public records. 24 of 24 data sources answered.
16 categories scored 0 to 10 and weighted to one composite; the five-step key above decodes it.

PLM-20261014151531
Generated 14 October 2026

Moderate, 2.3 of 10, led by geology and PFAS

813 N Franklin St, Tampa, FL 33602 receives an overall rating of MODERATE (2.3 out of 10), meaning most standard environmental concerns are low, but two findings stand out and deserve attention before closing.

The geology and PFAS scores are the most significant findings. The ground beneath this home is carbonate rock, karst-prone limestone of the Tampa Member, with dolostone, sand, clay, and coral present as secondary and incidental materials. Cavities and sinkholes are possible in this formation, and any surface spill can reach groundwater quickly because the karst structure offers little natural filtration. That finding scores HIGH (10.0/10, weight 7%). Separately, Peter O Knight airport, 2.5 miles away, is a public general-aviation airport with an AFFF firefighting capability, and its FAA record carries a military landing-rights flag. AFFF foam is a known PFAS source, and while no measured release has been confirmed, the screening score is HIGH (10.0/10, weight 4%). These two findings together define the practical risk picture for this home.

The regulatory-facility picture scores MODERATE (3.3/10, weight 18%). There are 708 EPA-regulated facilities within 2 miles, of which 302 hold RCRA hazardous-waste generator registrations and 7 are TRI reporters. No facilities within 2 miles are Superfund-listed or in significant non-compliance. The nearest facility with any hazardous designation is 1.2 miles away. Within a quarter mile there are 43 facilities, none in the higher tiers. The nearest EPA-regulated facility is FRANKLIN SITE. The coastal zone scores ELEVATED (6.7/10, weight 2%): the property sits within the coastal zone, meaning Coastal Zone Management Act permitting applies if you plan to build or add, and storm-surge modeling places it in a Category 3 hurricane surge zone. Wetlands score ELEVATED (6.7/10, weight 3%), with three types identified near the home: Estuarine and Marine Deepwater, Freshwater Emergent Wetland, and Riverine. There are 8 National Register listings within 500 meters, scoring MODERATE (3.3/10, weight 3%), and Hillsborough County falls in EPA Radon Zone 2 (moderate potential), also MODERATE (3.3/10, weight 2%). Wildfire hazard potential is WHP Class 3, MODERATE (3.3/10, weight 4%). On the positive side, the home is in FEMA Flood Zone X, a minimal flood hazard area (LOW, 0.0/10), air quality is AQI 43 (Good) (LOW, 0.0/10), no underground or leaking storage tanks were found, no pipelines exist within 5 kilometers, no listed species or critical habitat were identified within 2 kilometers, no conservation easements appear within 500 meters, and seismic risk is Seismic Design Category A with an SDS of 0.04g (LOW, 0.0/10). There are 15 schools or daycares within 1 mile, 5 within a half mile, and 1 within a quarter mile, with the nearest at 0.227 miles.

Next steps before closing: the insurer's sinkhole coverage, given the carbonate rock; a PFAS tap-water or well test, which is how to know, or the utility's PFAS results.

708	X	43	0
EPA FACILITIES	**FEMA FLOOD ZONE**	**AIR QUALITY INDEX**	**LEAKING TANKS**
regulated facilities within 2 mi (EPA ECHO)	minimal flood hazard area	good, at the time of this report, 0 to 500 scale	leaking underground storage tanks on record

16 CATEGORIES · LEVEL, SCORE OF 10, WEIGHT IN THE COMPOSITE, FINDING Composite 2.3 of 10 · Moderate

Rating key Low Moderate Elevated High Severe

Each section is scored 0 to 3 and shown as 0, 3.3, 6.7 or 10; the composite is the weighted sum; the word is its band.

§	CATEGORY	LEVEL	SCORE	WEIGHT	FINDING
01	Facility proximity	Moderate	3.3	18%	708 EPA facilities within 2 mi; 7 TRI, 302 RCRA
02	Storage tanks	Low	0.0	15%	No underground storage tanks or leaking USTs found
03	Flood	Low	0.0	12%	Zone X, minimal flood hazard area
04	Wetlands	Elevated	6.7	3%	3 wetland types identified, significant coverage near site
05	Air quality	Low	0.0	5%	AQI 43, good, at the time of this report
06	Soil and geology	High	10.0	7%	Carbonate rock, karst-prone (limestone, Tampa Member)
07	Seismic	Low	0.0	8%	Seismic Design Category A, SDS 0.04 g
08	Wildfire	Moderate	3.3	4%	WHP class 3, moderate, state-level estimate
09	Listed species	Low	0.0	6%	No listed species or critical habitat within search radius
10	Historic register	Moderate	3.3	3%	8 National Register listings within 500 m
11	Coastal zone	Elevated	6.7	2%	Within coastal zone, CZMA permitting applies
12	Conservation easements	Low	0.0	4%	No conservation easements within 500 m
13	PFAS	High	10.0	4%	Peter O Knight 2.5 mi: potential PFAS source, not measured
14	Pipelines	Low	0.0	4%	No pipelines identified within 5 km
15	Landslide	Low	0.0	3%	Low landslide susceptibility, no deposits in search radius
16	Radon	Moderate	3.3	2%	EPA Radon Zone 2 (moderate potential), Hillsborough County

Recommendation. *Next steps before closing: the insurer's sinkhole coverage, given the carbonate rock; a PFAS tap-water or well test, which is how to know, or the utility's PFAS results.*

READING THIS TABLE

Level	The category's own five-step word, Low to Severe, from its score of 10.
Score	The category's own score, 0 to 10, before weighting.
Composite	The weighted sum of the scores, here 2.3 of 10; the cover key maps it to the rating.
Not assessed	No usable data returned; no score, and the composite is computed without it.
Ladder	Five ticks filled to the step: one for Low, five for Severe.
Weight	The category's share of the composite; the weights sum to 100 percent.
Severe	Not a composite band: a Superfund NPL site within 0.5 mi sets it directly.
Finding	One line; the section pages carry the full finding, map and sources.

Scores and weights: Groundsheet risk scorer, this run · findings: the section sources listed on the data sources page · generated 14 October 2026 · report PLM-20261014151531

Sixteen sections screened: two High, two Elevated, four Moderate, eight Low

Every section in one ledger with its level on the five-step ladder. The highest level, High, falls on Geology and soil, PFAS[k] (airports). Sections with a page of their own are marked; the rest are screening results only.

SECTION	LEVEL	WHAT WAS FOUND	DETAIL
Regulated facilities (EPA, RCRA)	Moderate	708 EPA-regulated facilities within search area. 7 TRI[k] reporters; 302 RCRA[k] generator registrations.	Own section
Storage tanks (UST, LUST)	Low	No underground storage tanks or leaking USTs found. Registered tanks (UST[k]): 0; leaking tanks (LUST[k]): 0.	Own section
Flood zone	Low	**Zone X**: Area of minimal flood hazard (outside 0.2% annual chance). Special Flood Hazard Area (SFHA[k]): no.	Own section
Wetlands	Elevated	Wetlands present within the screening frame: yes. NWI[k] types: Estuarine and Marine Deepwater, Freshwater Emergent Wetland, Riverine.	Own section
Air quality	Low	AQI[k] 43 (Good) at the time of this report. Primary pollutant: PM2.5[k] (AQI 15), O3[k] (AQI 43), PM10[k] (AQI 9). Multi-year EPA[k] AQS[k] readings are on the air quality page.	Own section
Geology and soil	High	Rock type limestone (dominant), dolostone, sand, and clay (secondary), coral (incidental); unit Tampa Member. Age Chattian - Middle Miocene (11.63 - 27.3 Ma). Foundation class good; carbonate rock, karst-prone: cavities and sinkholes possible (Macrostrat potential field: none). Major: {limestone}, minor:{dolostone,sand,clay}, incidental:{coral} bedrock: good foundation, difficult excavation difficulty.	Own section
Groundwater wells	Context	**50 wells** on record: 0 within 0.25 mi, 17 within 0.5 mi, 47 within 1 mi. Predominant use Irrigation (IR). Aquifer Floridan Aquifer System. Source: USGWD[k].	Own section
Seismic hazard	Low	Seismic Design Category A: low seismic activity (SDS[k]: 0.04g). SDC [k] **A** B C D E F SDS 0.041 g; PGA[k] 0.0272 g (ASCE 7[k]).	Screening only
Wildfire	Moderate	WHP[k] Class 3: Moderate wildfire hazard potential (state-level estimate for Florida). WHP class on the five-step scale: **Moderate** (very low, low, moderate, high, very high). 8 historical fire perimeters recorded within 30 mi (NIFC[k]).	Own section
Pipelines	Low	No pipelines identified within 5km. 0 segments within 1 km, 1 within 5 km; nearest 5.35 km. Operator: Florida Gas Trans Co. Hazardous liquid lines: none (EIA[k] public geometry, generalised).	Own section
Landslide	Low	Low landslide susceptibility: no deposits found within search radius.	Screening only
Radon	Moderate	EPA[k] Radon Zone 2 (moderate potential): Hillsborough County. Zone meaning: Moderate Potential (2-4 pCi/L[k]). Testing recommended; the zone is a county average, not a reading at this address.	Own section
Listed species	Low	No listed species or critical habitat within search radius. No critical habitat or listed species found within 2km	Screening only
Historic register	Moderate	8 National Register listing(s) within 500m. NRHP[k] listings within 500 m count; a listing nearby can bring Section 106[k] review to federally funded or permitted work.	Own section
Coastal zone	Elevated	Inside a CZMA[k] coastal zone (Storm Surge (by Hurricane Category): 3); additional permitting applies to development within coastal boundaries. State layer FL_FloodComposite.	Screening only

Environmental findings *continued*

SECTION	LEVEL	WHAT WAS FOUND	DETAIL
Conservation easements	▮□□□□ Low	No conservation easements within 1 mile (NCED[k]). Protected lands nearby (PAD-US[k]): Curtis Hixon Waterfront Park, Oaklawn Cemetery, Tampa Riverwalk and 10 more.	Screening only
PFAS (airports)	▮▮▮▮□ High	Peter O Knight 2.5 mi away: a potential PFAS[k] source (AFFF[k] firefighting foam), not a measured release; high screening score. A public general-aviation airport with an AFFF firefighting capability. The FAA[k] record carries a military landing-rights flag, which sets the high score. Nearest AFFF-candidate airport: Peter O Knight (2.5 mi, public general-aviation airport with an AFFF firefighting capability). A potential source within 3 miles; a tap-water or well PFAS test is how to know. PFAS screening of groundwater and soil recommended.	Screening only
Sensitive receptors	Context	1 within 0.25 mi, 5 within 0.5 mi, **15 within 1 mi** (OSM[k]). Nearest: Unnamed facility (0.23 mi), Sam Rampello Downtown Partnership School (0.46 mi), Tampa Preparatory School (0.47 mi), USF Center for Advanced Medical Learning (0.49 mi), Unnamed facility (0.50 mi).	Own section

READING THIS SECTION

[k] marks a code defined in the codes key, pages 36 to 40.


▮▮▮□□	**Ladder.** Five ticks, filled to the level's step: Low 1, Moderate 2, Elevated 3, High 4, Severe 5. The word beside it carries the same fact in print without colour.
Own section	The section has a page of its own earlier in this report with the map, the figures and its own key. **Screening only**: the result is this line; no dedicated page was warranted.
Context	A row that informs but is not scored and carries no weight in the composite.
Checks: passed	Cover foot line: a consistency check of the retrieval, not a verification of the records.
CZMA	Coastal Zone Management Act: state review of development in the coastal zone.
EPA	US Environmental Protection Agency.
RCRA	Resource Conservation and Recovery Act, the federal hazardous-waste programme; each handler carries one designation (LQG, SQG, VSQG or TSD), set by the waste it generates in a month or whether it treats others' waste.
TRI	Toxics Release Inventory: annual chemical-release reporting by larger facilities.
LUST	Leaking underground storage tank.
UST	Underground storage tank, registered with the state or EPA.
SFHA	Special Flood Hazard Area, the 1-percent floodplain; insurance mandatory on federally backed loans.
Zone X	FEMA minimal risk (unshaded) or moderate, the 500-year floodplain (shaded).
NIFC	National Interagency Fire Center, the historical fire perimeter record.
WHP	USFS Wildfire Hazard Potential, a five-class national raster (very low to very high).
ASCE 7	The structural load standard that defines the seismic design values printed here.
PGA	Peak ground acceleration, in g (share of gravity).
SDC	Seismic Design Category, ASCE 7: A (lowest) to E/F, from design accelerations and soil.
SDS	Design spectral acceleration at short periods (ASCE 7), in g; governs low, stiff buildings.
USGWD	United States Groundwater Well Database, 14.2 million well records.
pCi/L	Picocuries per litre of air, the US radon unit; about 37 becquerels per cubic metre.
NWI	USFWS National Wetlands Inventory, mapped from imagery.
EIA	US Energy Information Administration, publisher of the generalised public pipeline geometry.
AFFF	Aqueous film-forming foam, the PFAS-bearing firefighting foam used at airports and bases.
FAA	Federal Aviation Administration, the airport and heliport register.
NCED	National Conservation Easement Database.
NRHP	National Register of Historic Places.
OSM	OpenStreetMap, the volunteer world map queried for schools, clinics and hospitals.
PAD-US	USGS Protected Areas Database of the United States.
PFAS	Per- and polyfluoroalkyl substances, persistent industrial chemicals ("forever chemicals").
Section 106	NHPA review federal agencies run before permitting or funding work near a listed historic property.
AQI	Air Quality Index, EPA's 0 to 500 scale; six bands, Good to Hazardous.
AQS	EPA Air Quality System, the archive of certified monitor readings behind the almanac.
O3	Ozone, a ground-level pollutant; AQS parameter 44201.
PM10	Coarse particles under 10 micrometres, in µg/m³.
PM2.5	Fine particles under 2.5 micrometres, in µg/m³; AQS parameter 88101.

Provenance: report PLM-20261014151531 · 16 scored sections and 2 context rows · levels from the Groundsheet scorer · sources queried 14 Oct 2026, 3:15 PM PT

813 N FRANKLIN ST, TAMPA, FL, 33602 · PLM-20261014151531

708 EPA-regulated facilities *within two miles.*


7 fall in Tier II[k] (elevated) — concentrated 1.20 mi E (76°). No Tier I designations within 2 mi. 369 Tier III standard permits and 332 Tier IV registrations account for the balance — composition, not volume, is the relevant lens here.



n Tier II · elevated · keyed n = table row n · Tier III · standard · Tier IV · registration · Subject (crosshair)

Tier II emission ticks: air ↑ · water ↓ · land → (one tick per medium released)

WIND ROSE



ORIENTATION · N = TRUE NORTH
PREVAILING NE 9% · CALM 13% · KTPA

SCALE — STATUTE MILES

0 0.5 1 mi

R.F. ≈ 1:76,312

PROJ Web Mercator EPSG:3857 · DATUM WGS 84
CENTER 27°57′04″N 82°27′34″W · zoom 12.27 · res 13.999 m/px
SOURCES EPA ECHO · RCRAInfo · TRI RY2024 · drains to McDill Air Force Base-Frontal Tampa Bay
RETRIEVED 14 October 2026 · ACCURACY parcel-class subject / meter-class overlays

43	125	326	708
WITHIN 0.25 MI	WITHIN 0.5 MI	WITHIN 1.0 MI	WITHIN 2.0 MI
0 elevated · 0 critical	0 elevated · 0 critical	0 elevated · 0 critical	7 elevated · 0 critical

Elevated = Tier II · Critical = Tier I

SOURCE EPA ECHO consolidated facility search · RCRAInfo generator tier · TRI reporting year 2024 · retrieved 14 October 2026 · accuracy: parcel-class for subject, meter-class for facility overlays

POWERED BY SLIPSTREAM

NEAREST FACILITIES BY SEVERITY

Tier I & II · top 7 of 7 within 2 mi

#	Sev	Facility	Designation	Status	Distance	Bearing	Δ elev
TIER I · CRITICAL 0 within 2 mi							
No Superfund (NPL), LUST, RCRA-TSD, or SNC designations within 2 mi.							
TIER II · ELEVATED nearest 7 of 7 within 2 mi							
1		**INTERNATIONAL SHIP REPAIR & MARINE SERV.** 1616 PENNY STREET	TRI Reporter transportation equipment 21,900 lb/yr xylene (mixed isomers) (air, water) 2020–2024 this facility's on-site release by year, large dot the latest year · --- sector median across 136 peers (same chemical, same industry group) · each dot a reporting year 11,600 lb/yr n-butyl alcohol (air, water) 2020–2024 (3 of 5 yrs)	Active enforcement inspected 2026-02	1.20 mi	→ E (76°)	−11 ft
2		**GULF MARINE REPAIR CORP** 1800 GRANT ST	TRI Reporter transportation equipment 32,700 lb/yr xylene (mixed isomers) (air) 2020–2024 20,000 lb/yr n-butyl alcohol (air) 2020–2024	In compliance inspected 2025-11	1.22 mi	↘ E (112°)	−12 ft
3		**ASSOCIATED ASPHALT TAMPA LLC** 500 19TH ST N	TRI Reporter petroleum bulk terminals polycyclic aromatic compounds: peak 203 lb/yr 2022, no release 2023–2024 2020–2024 benzo[g,h,i]perylene: reported, no release	In compliance	1.30 mi	→ E (88°)	−13 ft
4		**MARATHON TAMPA TERMINAL** 425 SOUTH 20TH STREET	TRI Reporter petroleum bulk terminals 3,200 lb/yr n-hexane (air) 2020–2024 2,600 lb/yr toluene (air) 2020–2024	Active enforcement inspected 2025-07	1.37 mi	→ E (102°)	−15 ft
5		**CITGO PETROLEUM CORPORATION** 801 MCCLOSKEY BLVD	TRI Reporter petroleum bulk terminals 900 lb/yr toluene (air) 2020–2024 (3 of 5 yrs) 500 lb/yr n-hexane (air) 2020–2024 (3 of 5 yrs)	In compliance inspected 2024-06	1.58 mi	↘ SE (146°)	−12 ft
6		**ARGOS USA, LLC** 2001 MARITIME BLVD.	TRI Reporter nonmetallic mineral product lead compounds: reported, no release mercury compounds: reported, no release	In compliance inspected 2025-03	1.69 mi	↘ SE (135°)	−13 ft
7		**TAMPA SHIP, LLC** 1130 MC CLOSKY BLVD.	TRI Reporter transportation equipment 14,200 lb/yr xylene (mixed isomers) (air) 2020–2024 ethylbenzene: peak 6,611 lb/yr 2022, no release 2024 2020–2024 (3 of 5 yrs)	In compliance inspected 2025-06	1.91 mi	↘ SE (149°)	−12 ft

SOURCE EPA ECHO · RCRAInfo generator tier · TRI 2024 · retrieved 14 October 2026. Tier mapping is Groundsheet's internal scheme, not EPA classification.

TIER III · STANDARD · NEAREST-IN-VICINITY CONTEXT

nearest 10 of 369 within 2 mi

#	Sev	Facility	Designation	Status	Distance	Bearing	Δ elev
1	●	**TAMPA ELECTRIC CO PLAZA GARAGE** 702 N FRANKLIN ST	RCRA electric utility	In compliance	0.04 mi	↘ SE (140°)	+1 ft
2	●	**UNLIMITED PRINTING & COPYING** 202 E CASS ST	RCRA printing / copying	In compliance inspected 2012-12	0.08 mi	↖ NW (323°)	−1 ft
3	●	**PIONEER AUTO SERVICE CENTER** 1004 N TAMPA ST	RCRA auto services	In compliance	0.13 mi	↖ NW (312°)	±0 ft
4	●	**USGSA** 601 N FLORIDA AVE	RCRA	In compliance	0.13 mi	→ E (106°)	+1 ft
5	●	**THE CLOTHES HAMPER** 201 E TWIGGS STREET	CAA Permit	In compliance	0.14 mi	↓ S (177°)	−2 ft
6	●	**UP TO DATE CLEANERS INC** 201 E TWIGGS STREET	CAA Permit dry cleaning / laundry	In compliance	0.14 mi	↓ S (177°)	−2 ft
7	●	**USGSA** 501 E POLK ST STE 600	RCRA	In compliance	0.16 mi	↗ NE (60°)	+2 ft
8	●	**CURTIS HIXON CONVENTION CENTER** 600 N ASHLEY DR	RCRA	In compliance	0.18 mi	↓ S (202°)	−5 ft
9	●	**CVS PHARMACY #4181** 220 E MADISON ST	RCRA	In compliance inspected 2014-08	0.19 mi	↓ S (164°)	−1 ft
10	●	**AUTOMOTIVE SERVICES** 601 N MORGAN ST	RCRA auto services	In compliance	0.20 mi	→ E (103°)	+2 ft

332 Tier IV facilities (registration-only) within 2 mi counted in density but not listed. Nearest: FRANKLIN SITE at 0.01 mi NW (295°) — plain FRS registration, no known release or enforcement.

SOURCE EPA ECHO · RCRAInfo generator tier · TRI 2024 · retrieved 14 October 2026. Tier mapping is Groundsheet's internal scheme, not EPA classification.

DESIGNATION REFERENCE

Scoped to codes appearing in this property's findings · full catalogue in § 09 methodology

TRI *Toxic Release Inventory* — TIER II

Facility manufactures, processes, or uses toxic chemicals above reporting thresholds and reports annual releases to air, water, and land.

RCRA *Resource Conservation and Recovery Act* — TIER III

RCRA-regulated facility with unspecified generator tier. Treated as Tier III unless enforcement history indicates otherwise.

CAA *Clean Air Act permit* — TIER III

Facility holds an air-emissions permit. Spans major industrial emitters to minor sources. A permit alone without violation is low-concern.

RECOMMENDATION The 7 Tier II facilities are the primary scoping inputs from this section. Phase I should assess proximity in context of the specific transaction. The 332 Tier IV registrations collectively signal industrial history that state database review may enrich.

SOURCE EPA ECHO · RCRAInfo generator tier · TRI 2024 · retrieved 14 October 2026. Tier mapping is Groundsheet's internal scheme, not EPA classification.

Reading this section.

A self-contained vocabulary for the EPA facility findings above, no jargon assumed.

k after a tier on page A marks a code defined in the codes key at the end of the report.

GROUNDSHEET TIER
I / II / III / IV

Groundsheet's own four-tier scheme, not an EPA classification. It ranks EPA facility designations by severity. **Tier I (critical)** covers Superfund NPL, LUST, RCRA-TSD, and Significant-Non-Compliance enforcement. **Tier II (elevated)** covers RCRA Large-Quantity Generators and TRI reporters. **Tier III (standard)** covers all other RCRA-permitted facilities. **Tier IV (registration)** covers FRS registrations with no release or enforcement record. EPA publishes the designations; the tier is Groundsheet's reading of them, and the raised k after a tier on page A points to the codes key at the end of the report.

TIER I TRIGGERS
NPL · LUST · RCRA-TSD · SNC

The four federal designations that raise a facility to **Tier I (critical)**: **NPL** — National Priorities List (Superfund) sites; **LUST** — Leaking Underground Storage Tank; **RCRA-TSD** — a RCRA Treatment, Storage & Disposal facility; **SNC** — Significant Non-Complier under active EPA enforcement. Any one is sufficient to key the facility on the plate.

EXPOSURE PATHWAY
Why proximity is screened

Facility proximity is screened as a proxy for the three physical routes by which a regulated release can reach the subject — **air** (airborne emissions and drift), **water** (surface runoff and groundwater), and **land** (soil and waste handling). Tier II callouts carry an emission tick per medium released by the chemicals listed for that facility, latest reporting year (air ↑ · water ↓ · land →); distance and bearing situate the subject relative to those routes. Screening flags what warrants a closer look — it does not model dispersion or establish exposure.

WITHIN 2 MI
Screening radius

Facilities are screened within a **2-mile geodesic radius** of the subject parcel centroid. Distance bands of 0.25 mi, 0.5 mi, 1.0 mi, and 2.0 mi report concentric counts so the reader sees the falloff with distance — not just the total.

BEARING
8-point compass

Bearing from subject to facility, reported as 8-point compass (N, NE, E, SE, S, SW, W, NW) plus the precise angle in degrees clockwise from true north. **0° = N**, **90° = E**, **180° = S**, **270° = W**.

Δ ELEV
NAVD 88

Elevation difference between facility and subject, in feet, referenced to **NAVD 88** (North American Vertical Datum of 1988). Positive = facility above subject; negative = below. Em-dash where USGS 3DEP elevation is off-coverage.

STATUS
EPA ECHO compliance

Each facility's federal compliance snapshot from EPA ECHO. **Significant violator** flags significant non-compliance (SNC) or a significant-violation history; **Active enforcement** marks an open enforcement action; **In compliance** indicates no current violations of record. The mono line below (**inspected YYYY-MM**) gives the most recent EPA-recorded formal inspection, where one exists.

Reading this section.

Continued: the vocabulary for the EPA facility findings above.

EPSG 3857 · WGS 84 Projection + datum	**Web Mercator (EPSG 3857)** for the survey-plate basemap; **WGS 84** as the horizontal datum for all coordinates. The plate renders on a clean, muted survey ground (no topographic underlay) so the ring geometry, keyed callouts, and collar apparatus carry the reading.
CROSSHAIR Subject property	The crosshair at plate center marks the subject parcel; every distance and bearing in this section is measured from it.
WIND ROSE Orientation instrument	The wind rose orients the plate to true north (**N = true north**) and serves as the orientation instrument — there is no separate north arrow. Where station data exists it also reports the prevailing wind direction and calm frequency.
R.F. · SCALE Representative fraction	The **representative fraction** (R.F. ≈ 1:N) states the map-to-ground ratio at plate center; the graphic scale bar reads directly in statute miles and stays true if the page is resized.
EPA ECHO Enforcement & Compliance	The **EPA Enforcement and Compliance History Online** consolidated facility search — the federal source of record for facility-level compliance status, inspection history, and program flags across RCRA, CAA, CWA, SDWA, and CERCLA.
RCRA · TRI Resource Conservation · Toxics Release	**RCRAInfo** generator tiers (LQG / SQG / VSQG / TSD) drive the Tier II elevated classification for large generators. **TRI** (Toxics Release Inventory) annual chemical-release submissions identify reporters and surface per-chemical release volumes per year.
TRI REPORTER SPARKLINE Line · dashed line · dots · years	The small chart under a TRI reporter's chemical line. The **solid line** is that facility's annual on-site release of the chemical, in pounds, by year. The **dashed line** is the **sector median**: the median annual release of the same chemical among TRI facilities in the same industry group (the first three digits of the industry classification code EPA records for each facility), so the reader sees whether this facility runs above or below its peers; the number of peers is printed in the legend under the first sparkline when known. The **dots** are reporting years, the **larger dot** the latest year; a missing dot is a year with no TRI submission. The **year range** beside the chart is the reporting window (for example 2020 to 2024), with the count of reported years when some are missing. Magnitude is in the figure on the line above; the chart shows shape only.


A screening output, not a Phase I Environmental Site Assessment, an insurance determination, or a substitute for site-specific investigation.

SOURCES EPA ECHO consolidated facility search · RCRAInfo generator tier · TRI reporting year 2024 · further reading: epa.gov/enviro/facts-and-figures

Zone X *an area of minimal flood hazard.*

The subject lies outside the mapped 1-percent-annual-chance floodplain, which FEMA[k] (Federal Emergency Management Agency) calls the Special Flood Hazard Area, SFHA[k]. Mandatory flood insurance does not apply. Elevation and the distance to the nearest mapped flood polygon still belong in the diligence record.

§ 02 · FIG. 1 · FEMA FLOOD ZONES · 3D TERRAIN CONTEXT



FEMA FLOOD ZONES


- **VE / V** coastal, wave action, 1 percent annual chance
- **A / AE** 1 percent annual chance, base flood elevation where mapped
- **AH / AO** shallow flooding, 1 to 3 ft
- **X shaded** 0.2 percent annual chance or behind a levee
- **X** minimal hazard
- **D** undetermined
- Open water, not a flood class; letters on the map name each zone

basemap Mapbox Satellite Streets
proj EPSG 3857 · WGS 84
datum V. NAVD 88
elev (subj) 18 ft
source FEMA NFHL
record 13 Oct 2026
geometry live, October 14, 2026 (PDT)

X	No	0.17 mi	18 ft
FEMA ZONE	INSIDE SFHA[k]	NEAREST MAPPED SFHA	SUBJECT ELEV · NAVD 88
low risk · record 13 Oct 2026	A · AE · AH · AO · VE · V	bearing SW	USGS 3DEP

SOURCE FEMA National Flood Hazard Layer (NFHL) · zone record retrieved 13 Oct 2026 · plate geometry retrieved October 14, 2026 (PDT) · relief USGS 3DEP · retrieved 26 Mar 2026 · accuracy: parcel-class for subject, polygon-class for flood polygons (FEMA NFHL effective panels)

§ 02 · FIG. 2 · PARCEL DETAIL · TOP-DOWN (NEAREST SFHA 0.17 MI SW)



Detail: the nearest mapped flood zone relative to the parcel. Top-down view, north up; the same FEMA palette as the primary map, each polygon lettered with its zone. Zones in view: A / AE, X shaded and X. Nearest flood zone to the parcel: Zone AE, 0.17 mi SW, 1 percent annual chance. The zones drawn here come from an area query made for this figure.

WHAT YOU CAN DO

4 steps · Zone X, inside a surge zone · sources linked

01 Zone X still floods: about a quarter of flood claims come from outside the mapped floodplain, and the low-risk policy costs least, so get a quote before closing. floodsmart.gov

02 Check the effective flood map panel and any revision in progress at the map service center; the nearest mapped zone is 0.17 mi SW. msc.fema.gov

03 Ask the seller in writing about water in the crawlspace, basement or garage and about any past claim on the building. fema.gov

04 The parcel lies in a county storm-surge evacuation zone: look up the zone letter and the route before hurricane season. floridadisaster.org

SOURCE FEMA National Flood Hazard Layer (NFHL) · area query retrieved October 14, 2026 (PDT) · zoom 15.5 top-down · accuracy: parcel-class for subject, polygon-class for flood polygons

§ 02 · SECTION REFERENCE

Plain-language terms *flood and terrain.*

Every term this section uses, defined for a non-specialist. Included here so the reader has a self-contained reference; in the assembled document this material is consolidated in the codes key at the tail.

FEMA flood zone classes

- **Zone VE / V**: the highest-risk coastal areas, exposed to wave action during a major flood. Mandatory flood insurance.
- **Zone A / AE**: the 100-year floodplain, areas with a 1 percent chance of flooding in any given year. The core Special Flood Hazard Area. Mandatory flood insurance.
- **Zone AH / AO**: areas of shallow flooding, typically 1 to 3 ft of ponding or sheet flow during the base flood.
- **Zone X (shaded)**: the 500-year floodplain, a 0.2 percent annual chance of flooding, or areas protected by a levee. Insurance recommended, not required.
- **Zone X (unshaded)**: minimal flood hazard; outside the mapped floodplain.
- **Zone D**: flood hazard undetermined; no analysis has been completed for the area.

SFHA, Special Flood Hazard Area

The land FEMA expects to be inundated by the 1-percent-annual-chance (100-year) flood. Federally backed mortgages on property here require flood insurance.

"100-year" / "500-year" flood

Annual probability, not frequency: a 100-year flood has a 1 percent chance in any year, and can occur in consecutive years; a 500-year flood has a 0.2 percent chance.

Behind levee

Land protected by a flood-control levee. Mapped at reduced risk while the levee is certified, but residual risk remains if the levee is overtopped or fails.

Open water

Surface water (rivers, lakes, bays, ocean) mapped by the FEMA NFHL but not assigned a flood-zone classification. Rendered with a hatched fill on the map so the satellite imagery underneath shows the real water surface.

Base Flood Elevation (BFE)

The height floodwater is expected to reach during the 1-percent-annual-chance flood, in feet NAVD 88. Used to set how high structures must be built to be considered above the design flood; compare subject elevation against BFE to read freeboard.

NAVD 88

North American Vertical Datum of 1988, the modern reference surface for elevations. A flood report measures the property's height against this so it can be compared to BFE and other flood elevations.

WGS 84

World Geodetic System 1984, the horizontal reference for the latitude and longitude coordinates locating the property.

FEMA NFHL

National Flood Hazard Layer, FEMA's official digital flood-map database. The legally in-force maps are issued as effective FIRM panels (Flood Insurance Rate Maps); the record date stamps which panel was in force when the zone was read.

Zone record and plate geometry

The subject's zone is read from one NFHL point record, dated in the collar; a separate live query fetches that zone's outline for the plate. If the outline fails, the zone stands and the page says so; if no record returns, no zone is printed and the section is not assessed.

USGS 3DEP

U.S. Geological Survey 3D Elevation Program, the source of the terrain and elevation data used for relief and subject elevation.

Subject elevation

Ground elevation at the parcel coordinate, in feet NAVD 88, from USGS 3DEP. Read against the base flood elevation on the FIRM panel: the difference is the parcel's height above or below the design flood.

Web Mercator (EPSG:3857)

The map projection used to render the maps; the standard for web and satellite basemaps. EPSG is the registry of coordinate systems that numbers it.

Five-class blue palette

Flood-zone fills run darkest (VE / V, highest hazard) to lightest (X, minimal hazard), with wide steps so the five classes read apart in print, and each polygon carries its zone letters. A parcel in Zone X reads as the faintest tint by design.

Parcel-class vs polygon-class accuracy


The subject location is resolved to parcel-level precision. Flood-zone boundaries are drawn at the resolution of FEMA's mapped polygons, which are regional-scale and not survey-grade. Boundaries close to a property should be confirmed by survey, not read to the foot off this map.

Parcel-detail inset

The close-up top-down map that appears when a mapped flood zone falls near the subject, showing how close the nearest flood zone comes to the property. It is omitted when the nearest flood zone is far away.

Moderate wildfire hazard, *8 fires within thirty miles.*

The subject parcel sits in WHP Class 3 — Moderate. The surrounding region carries a substantial recent record: 8,181 acres burned within thirty miles since 2016, including the Anclote Branch · 2017 at 2,510 acres.



WILDFIRE HAZARD POTENTIAL · USFS

V LOW · LOW · **MOD** · HIGH · V HIGH

Burn perimeter (≥ 100 ac)

Subject property

basemap Mapbox Satellite

proj EPSG 3857 · WGS 84

source USFS Wildfire Hazard Potential

retrieved 14 October 2026

8	8,181	2,510	Class 3 Moderate
FIRES RECORDED	ACRES BURNED	LARGEST FIRE (AC)	WHP AT PARCEL
within 30 mi · since 2015	cumulative · within 30 mi	Anclote Branch · 2017	USFS probabilistic raster

Recent burn perimeters, *within reach.*


The ten largest burns within thirty miles of the parcel since 2015, by acreage. The locator places each perimeter by its true position and extent relative to the property.

RECENT FIRE HISTORY · WITHIN 30 MI · 2015–PRESENT

	FIRE NAME	YEAR	ACRES	DISTANCE
1	Anclote Branch	2017	2,510	21.0 mi N
2	CR640 (53)	2022	1,478	26.7 mi E
3	New Wales (53)	2022	976	28.5 mi E
4	New Wales (53)	2024	810	26.2 mi SE
5	Henry George Road	2021	641	21.5 mi E
6	Thatcher	2016	638	23.6 mi SE
7	New Wales	2024	607	27.9 mi SE
8	POWERLINE640	2020	521	27.9 mi E

All qualifying burns (≥ 100 ac, since 2015) shown; no continuation.

LOCATOR · PERIMETERS WITHIN 30 MI



Overhead view, perimeters to scale. Subject property at the blue pin. Numbers key to the table. No hazard shading, geometry only.

WHAT YOU CAN DO

4 steps · class 3 of 5 · sources linked

01 Keep a 30-foot lean, clean and green zone: mown grass, no dead fronds or pine straw against the walls, firewood stacked away from the house. fdacs.gov

02 Screen vents and soffits with fine metal mesh and keep the roof and gutters clear of needles and leaves, the places embers land. ready.gov

03 Most Florida wildfires start in the dry spring: check the county burn ban before any yard burning, and keep a go-plan with two routes out. fdacs.gov

04 8 fires burned within 30 mi since 2015, the nearest 21 mi away; smoke travels, so pair this with the air-quality steps in § 09. fire.airnow.gov


Source USFS Wildfire Hazard Potential (probabilistic raster, parcel-class lookup) · burn perimeters via NIFC InterAgency Fire Perimeter History and MTBS burned-area boundaries (≥ 100 acres, 2015–present) · distances geodesic to nearest perimeter edge · retrieved 14 October 2026.

Reading this section.

Plain-language notes on the terms, ratings, and data behind the wildfire pages. Each entry explains what a figure means, where it comes from, and what it does and does not establish for this property.

WILDFIRE HAZARD POTENTIAL
WHP · Class 1–5

A **USFS** (US Forest Service) rating of the relative likelihood that a parcel experiences wildfire, modeled from fuels, terrain, weather, and historical ignition patterns. It is a **probabilistic estimate of underlying potential**, not a prediction or a forecast. The five classes run Very Low to Very High; this property's class is marked on the scale.



CLASS 3 — MODERATE
this parcel

A Moderate WHP rating means the **setting** carries meaningful wildfire potential — independent of whether large fires have occurred nearby. The rating describes the standing landscape; the history describes what has burned.

BURN PERIMETER
≥ 100 acres

The mapped outline of a past fire's footprint. Groundsheet screens perimeters of **100 acres or larger** recorded **since 2015** within thirty miles of the property, and keeps fires of **20,000 acres or more** out to 50 miles, listed in grey and left out of the thirty-mile counts. Smaller fires, and fires before 2015, are not drawn: the threshold keeps the map to consequential, well-documented events.

RECENT FIRE HISTORY
30 mi · 2015–present

The roster of qualifying burns near the property over a fixed ten-year window. An empty roster is a genuine finding (no large fires recorded), **not** missing data. Distances are measured from the property to the **nearest edge** of each perimeter, by geodesic distance (straight-line across the curve of the earth).

BEARING NOTATION
8-point compass

Direction abbreviations next to each distance in the fire-history table: **N** north, **NE** northeast, **E** east, **SE** southeast, **S** south, **SW** southwest, **W** west, **NW** northwest. "27.1 mi NE" means 27.1 miles to the northeast of the subject property.

NIFC PERIMETER HISTORY
data source

The **National Interagency Fire Center** InterAgency Fire Perimeter History, the federal consolidated record of mapped fire footprints, merged with **MTBS** (Monitoring Trends in Burn Severity, every fire over 1,000 acres in the West and 500 in the East since 1984), the source for every perimeter and the fire-history table. The NIFC record is incomplete before 2021; MTBS fills those years with a one-to-two-year lag.

PROBABILISTIC RASTER
how WHP is read

The WHP rating is stored as a grid of pixels ("raster"), each carrying a hazard value. Groundsheet reads the value of the pixel at the property's coordinates — a **parcel-class lookup** — to report the WHP class for this specific location.

EPSG 3857 · WGS 84
projection · datum


Coordinate-system references in the map metadata. **WGS 84** is the global latitude/longitude datum used by GPS; **EPSG 3857** is the web-map projection used by Mapbox, Google Maps, and most online cartography.

A screening output, not a fire-risk forecast, an insurance determination, or a substitute for site-specific assessment.

Sources USFS Wildfire Hazard Potential · NIFC InterAgency Fire Perimeter History and MTBS burned-area boundaries · further reading: Ready.gov/wildfires.

50 wells in 2 mi, nearest at 0.34 mi

Every well on record within 2 mi in USGWD[k], the national table of well completion reports, from above; each well is one small circle, placed where the state filed it and coloured by its use. This state files position and use, not depth or yield.



subject · well: position and use · yield not recorded · rings every ½ mi · one snapped point, fanned · arterial road · water

USGWD completion reports 2023 · 14 Oct 2026 · north up
outer ring 1.5 mi, rings every ½ mi · box 5.3 x 3 mi, none past 1.2 mi · roads and water OpenStreetMap

50	n/r	0	0.34 mi
WELLS within 2 mi · 0 within ¼ mi	**MEDIAN WELL BOTTOM** not recorded in this table	**YIELD RECORDED** of 50	**NEAREST WELL** SW · irrigation well

One well, one glyph — drawn at the map's scale

one small circle: where the well is, what it is for
This state files where each well is and what it is for, not depth or yield, so every well is the same small circle.

Irrigation 35 · Industrial 1 · Unknown or other 14

colour = use; the ledger prints the use in words

Wells by distance

within ¼ mi	0
within ½ mi	17
within 1 mi	47
within 2 mi	50

Aquifer named for 50 of 50: Floridan Aquifer System. An aquifer is the water-bearing rock a well draws from.

WHAT YOU CAN DO

[k] = a code in the codes key at the end · sources linked

Nearest well on record: 0.34 mi SW, irrigation. No public-supply well, one feeding a drinking-water system, is on record within 2 mi.

01 On a private well, ask for the completion report, the static water level and a water test from the past year. floridahealth.gov


02 Test a private well yearly for bacteria and nitrate, and once for what the facilities in § 01 handle. epa.gov

03 On city water, read the system's annual water quality report: its source wells and every contaminant found. epa.gov

Seismic Design Category A: very low shaking

***Hawthorn Group, Arcadia Formation, Tampa Member**, Chattian to Middle Miocene, 12 to 27 Ma; shaking is not a design driver.*

Under the house: the mapped surface unit



at the surface; thickness not in the source

Hawthorn Group, Arcadia Formation, Tampa Member
mainly limestone, with dolostone, sand, clay, and traces of coral
Chattian to Middle Miocene
12 to 27 Ma

What it means: limestone dissolves slowly in rainwater: it makes firm ground but also cavities and sinkholes, and it moves groundwater fast through cracks and channels.

Foundation: good: firm ground for ordinary footings
Karst: carbonate rock, karst-prone; cavities and sinkholes possible (Macrostrat potential field: none)
Spill mobility: fast: a spill reaches groundwater quickly
Excavation: difficult: rock, blasting or heavy equipment

Where the unit sits in time



this unit: 12 to 27 Ma, Chattian to Middle Miocene

Ma = million years ago · square-root scale

⊙ subject ▭ unit's span in time

no state map: CGS covers California only · north up
Macrostrat 9 Oct 2026 · USGS ASCE 7-22 maps 9 Oct 2026

A very low	0.04 g	0.03 g	BC[k]
SEISMIC DESIGN CATEGORY	S_{DS} DESIGN SHAKING	PEAK ACCELERATION	SITE CLASS
SDC[k] · A to E, the scale below	share of gravity · S_{D1} 0.02 g	PGA[k] · 2% in 50 years	assumed · V_{S30} 760 m/s

A ◂ THIS SITE	B	C	D	E
very low shaking	low shaking	moderate shaking	high shaking	very high shaking

For a buyer. Category A means shaking strong enough to damage ordinary buildings is not expected; the code asks only for basic ties between structural parts. The design values assume firm ground, site class BC[k]. Wind and flood, not shaking, govern the structure here.

WHAT YOU CAN DO

3 steps · category A: the building, not the ground · sources linked

The design category describes the ground under the lot, not this building; what the building does with that shaking is for an inspector or a structural engineer to judge, and the steps below are about the building.

01 No seismic retrofit is called for at this category; the inspector's usual foundation and anchoring checks are enough. usgs.gov

02 The federal kit for storms covers an earthquake too: three days of water, food, medicines, a flashlight and a radio. ready.gov

03 Earthquake cover is a separate endorsement most owners here skip; the policy's wind and ground-movement terms matter more. ready.gov

Nearest wells on record from the map on page 1, use printed so the map reads without colour: 0.34 mi SW, irrigation · 0.34 mi SW, unknown or other · 0.40 mi SW, irrigation. Depth and yield are not in this state's table.

READING THIS SECTION


[k] marks a code defined in the codes key at the end of the report.

S_{DS} S_{D1} design shaking at 0.2 s (stiff low buildings) and at 1 s (tall, flexible ones), as a share of gravity; S_S 0.07 and S_1 0.03 g are the mapped values before the site adjustment. **ASCE 7-22** the load standard the building code adopts; values for Risk Category II, ordinary buildings, at the 2 percent in 50 years motion. **Ma** million years ago; Chattian: the late Oligocene, 23 to 28 million years ago; Middle Miocene: 12 to 16 million years ago. **Macrostrat** the geologic database that names the unit under the subject (no state plate like California's is published here).

USGWD HydroShare 2023, 14 Oct 2026 · USGS ASCE 7-22, 9 Oct 2026 · Macrostrat, 9 Oct 2026 · PLM-20261014151531

Limestone under the lot; 30 reported sinkholes within 5 mi

Tampa Member *(Arcadia Formation): limestone, 27 to 12 Ma; rock that dissolves. FGS[k] holds 30 subsidence incident reports within 5 mi, none within 1 mi, none verified by a geologist.*



subject · rapid: collapse · slow: subsidence · rate not recorded · size = width filed · carbonate at surface · buried, pseudokarst · water · 1 and 5 mi · arterial road

USGS OFR 2014-1156 polygons (2014), fetched 13 Oct 2026
FGS incident reports 1909 to 2026, fetched 13 Oct 2026
box 18 x 10 mi · 5 mi ring · 56 reports in frame
north up · roads and water OpenStreetMap

30	1.3 mi	*Limestone*	*Area III*
REPORTED INCIDENTS	**NEAREST REPORT**	**ROCK UNDER THE LOT**	**SINKHOLE TYPE AREA**
within 5 mi · 0 within 1 mi · FGS, 1909 to 2026	NW · 1985 · rate not recorded	Tampa Member, 27 to 12 Ma	FGS · abrupt, numerous · cover is 30 to 200 ft thick

What karst is. Ground on rock that dissolves: limestone, dolomite, gypsum. Slightly acid rainwater widens cracks into channels and cavities over thousands of years, and the cover of sand and clay on top falls or sags into them: sinkholes, caves, springs, streams that vanish underground. Here: the Tampa Member, mainly limestone, with dolostone, sand, clay, inside the USGS[k] "carbonate rocks at or near the land surface" area. FGS[k] sinkhole type Area III: cover 30 to 200 ft of clayey sediment; sinkholes most numerous, abrupt; cover-collapse dominates.

Two kinds of sinkhole. Cover-subsidence: sandy cover trickles slowly into the rock and a shallow bowl grows over years, cracking slabs and tilting floors. Cover-collapse: clayey cover bridges a cavity until it cannot and the ground opens in hours, the kind that reaches the news. Of the 30 reports within 5 mi, 12 were filed as rapid, 2 as slow, 16 without a rate; 6 reported damage. Positions are to the parcel or a survey square: where people reported movement, not exact spots.

Nearest report 1.3 mi NW, 1985; newest 2025

Every FGS[k] subsidence incident report within 5 mi, nearest first: a call or a claim, placed to the parcel or a survey square; the newest is 1.6 mi NE. "Verified" means a licensed geologist confirmed a sinkhole; most were never checked.

REPORTED INCIDENTS WITHIN 5 MI 30 reports · size = length x width x depth, ft, as filed · n/r = not recorded

REF	YEAR	MI	BEARING	SIZE FT	RATE	VERIFIED	DAMAGE	PLACED TO	NOTE, AS FILED
10-631	1985	1.3	NW	n/r	not recorded	unknown	unknown	parcel	Allstate claim cwp 12/5/85. ...
10-901	1989	1.3	NE	2 × 2 × 5 ft est.	rapid	unknown	yes	¼¼¼ section	Damage: collapse of roadwa...
10-075	2025	1.6	NE	4 × 4 × 4 ft est.	not recorded	no	no	unknown	Private Citizen reports a pot...
10-070	2024	1.8	ENE	n/r	not recorded	unknown	no	GPS	A private citizen reports a po...
10-037	1991	1.8	WSW	5 × 5 × 3 ft est.	rapid	unknown	yes	¼¼ section	
10-1124	2016	1.8	NE	n/r	not recorded	unknown	unknown	GPS	
10-997	2010	2.1	ENE	n/r	not recorded	unknown	unknown	parcel	2' dia and 4' deep formed at...
10-039	1991	2.3	N	6 × 6 × 3 ft est.	rapid	unknown	no	parcel	plotting at wrong street addr...
10-655	1987	2.8	W	2 × 2 × 30 ft est.	rapid	unknown	no	parcel	Telephone repairman was di...
10-1079	2012	3.1	NE	3.5 × 2.5 × 2.5 ...	rapid	unknown	unknown	parcel	3.5' long x 2.5' wide x 2.5' d...
10-998	2010	3.3	NNW	n/r	not recorded	unknown	unknown	¼¼¼ section	Depression formed 2 days p...
10-068	2023	3.4	NE	7 ft est.	not recorded	unknown	unknown	GPS	Private citizen in Tampa rep...

18 more within 5 mi, all beyond 3.4 mi, not listed; the map on page 1 plots every one.

What Florida law requires. Florida Statute 627.706 makes every property insurer cover catastrophic ground cover collapse, a defined event with four parts: an abrupt collapse of the ground cover, a depression clearly visible to the naked eye, structural damage to the building including its foundation, and the building condemned and ordered vacated. All four must hold; a cracked slab or a dip in the yard does not qualify. Insurers must also offer sinkhole loss cover, structural damage to the building including the foundation from sinkhole activity, as an option with its own premium and a deductible of 1, 2, 5 or 10 percent of the dwelling limit.

WHAT YOU CAN DO 4 steps · Florida: the statute and the register · sources linked

01 Order a sinkhole inspection to the statutory standard: ground-penetrating radar across the lot and borings to the limestone, by a licensed geologist or engineer. leg.state.fl.us

02 Ask the seller in writing whether a sinkhole claim was ever made on the property and whether the money went to repair; the statute requires the answer and the insurer files the report with the county clerk. leg.state.fl.us

03 Quote the sinkhole-loss endorsement before the offer (the standard policy covers only catastrophic ground cover collapse) and keep every repair record; a paid, unrepaired claim is often uninsurable. myfloridacfo.com

04 Report new ground movement to the state survey; it keeps the incident register this map draws from. floridadep.gov


READING THIS SECTION [k] marks a code defined in the codes key at the end of the report.

Karst ground on rock that dissolves in rainwater (limestone, dolomite, gypsum): sinkholes, caves, springs, streams that vanish underground. **Carbonate rock** limestone and dolomite, calcium or magnesium carbonate; slightly acid rainwater dissolves it along cracks, which makes karst. **Cover-collapse sinkhole** the sand or clay over a cavity bridges it until it cannot, then falls in within hours; the damaging kind. **Cover-subsidence sinkhole** sandy cover trickles slowly into the dissolved rock and the surface sags over years: a bowl, not a hole. **FGS** Florida Geological Survey, the state survey inside the Department of Environmental Protection. **SIR** Subsidence Incident Report, an FGS record of a reported depression or collapse; most are unverified citizen or insurer reports. **OFR 2014-1156** USGS Open-File Report 2014-1156 (Weary and Doctor), the national karst map; the hatched area on the map. **Area I to IV** FGS sinkhole type areas (Sinclair and Stewart 1985): I thin cover, few sinkholes; II sandy cover, gradual; III clayey cover, abrupt; IV deep cover, rare. **Catastrophic ground cover collapse** Florida Statute 627.706: abrupt collapse, a depression visible to the eye, structural damage including the foundation, and the building condemned; all four. **Sinkhole loss** Florida Statute 627.706: structural damage to the building including its foundation from sinkhole activity; optional cover every insurer must offer. **Placed to** how precisely a report was located: the parcel, a GPS fix, or a square of the survey grid (section 1 mi, ¼ section 160 acres, ¼¼ 40 acres, ¼¼¼ 10 acres). **Ma** million years ago. **E, B1, B2, B3** USGS exposure codes: E at or near the surface; B1 buried under 50 ft or less; B2 under more than 50 ft; B3 under less than 300 ft.

USGS OFR 2014-1156, Weary and Doctor 2014, fetched 13 Oct 2026 · FGS Subsidence Incident Reports, FDEP open data, fetched 13 Oct 2026, events 1909 to 2026 · FGS Sinkhole Types (Sinclair and Stewart 1985), 14 Oct 2026 · Macrostrat, 9 Oct 2026 · roads and water OpenStreetMap, Overpass · PLM-20261014151531

Moderate radon potential: EPA Zone 2, indoor radon predicted at 2 to 4 pCi/L.

Hillsborough County is designated Zone 2 by the US Environmental Protection Agency (EPA[k]): a predicted indoor radon concentration of 2 to 4 pCi/L[k], below the 4 pCi/L mitigation threshold but above ambient. The EPA recommends testing in Zone 2 counties; the actual concentration at this address is not known without direct measurement.



Zone 1 · 4 pCi/L or more Zone 2 · 2 to 4 pCi/L
Zone 3 · under 2 pCi/L Subject property · TAMPA
County line, state line heavier
Read: one fill per county, no finer

SOURCE EPA[k] Radon Zones · Census CBF[k] 500k 2024
BASEMAP © Mapbox[k], © OpenStreetMap[k] · RESOLUTION county
RETRIEVED 14 Oct 2026 · VINTAGE 1993 EPA zones
PROJECTION Web Mercator EPSG:3857[k] · WGS 84[k] · north up

2 of 3	4 pCi/L	*Not screened*	0.97 ppm eU
EPA PREDICTIVE ZONE	**EPA ACTION LEVEL**	**COUNTY INDOOR MEDIAN**	**SURFACE URANIUM · LOW**
predicted indoor average 2 to 4 pCi/L · county resolution	fix at or above it · consider fixing from 2 pCi/L	state indoor aggregate not yet wired for FL	below the national median of 1.6 ppm · USGS[k] NURE[k] survey, figure on page 3

RADON RISK · MODERATE ■■□□□ *Hillsborough County is EPA Zone 2, the middle of three predictive classifications.*

Radon (Rn-222[k]) is a colorless, odorless, radioactive gas produced by the decay of uranium and radium in soil and bedrock. It is the second-leading cause of lung cancer in the United States after tobacco and the leading cause among non-smokers. Radon enters buildings primarily through slab cracks, sump pits, and soil-gas intrusion at the foundation perimeter, where concentrations can accumulate to many multiples of outdoor ambient.

WHAT ZONE 2 MEANS AT THIS ADDRESS

a county prediction, not a measurement of this house

Hillsborough County's Zone 2 designation reflects a predicted indoor average **between 2 and 4 pCi/L[k], below the 4 pCi/L EPA[k] action level, but above outdoor ambient**. The county classification is derived from aeroradiometric uranium surveys, soil permeability, and aggregated indoor measurements. A Zone 2 finding does not indicate a mitigation requirement; it does mean the EPA recommends testing so that houses sitting above the county average can be identified and addressed.

Radon concentration varies house-to-house on the same street. Two adjacent homes with different basement configurations, foundation ages, and ventilation patterns can test at 1 pCi/L[k] and 6 pCi/L respectively, and in a Zone 2 county, the higher tail of that distribution regularly crosses the action level. A short-term test kit deployed in the lowest lived-in level of the structure for two to seven days is the informed next step, particularly if the home has a basement or slab-on-grade foundation.

Radon risk cannot be resolved through a Phase I Environmental Site Assessment: a Phase I does not test for radon. A Zone 2 finding does not mandate mitigation, but the EPA[k] does recommend testing, **particularly for homes with basements, slab-on-grade foundations, or substantial finished living space below grade**. *The in-house action here is a test kit, not a consultant.*

WHAT YOU CAN DO

4 steps · zone 2 · sources linked

01 Test before closing: a short-term kit in the lowest lived-in level with the house closed, 2 to 7 days; the state programme and hardware stores sell them for about 15 to 30 dollars. floridahealth.gov

02 At or above 4 pCi/L, follow with a 90-day test; that is the number a mitigation decision rests on. epa.gov

03 If the long test confirms it, hire a certified mitigator for a sub-slab vent system, usually 800 to 2,500 dollars installed, and make it a condition of the sale. epa.gov

04 Ask the seller for any past radon test or mitigation record; a fan already in place needs its own check. epa.gov


STATE INDOOR SURVEY · HILLSBOROUGH COUNTY

not screened

The Florida Department of Health, Radon Program indoor-measurement aggregate (county median, share of tested homes at or above 4 pCi/L[k], homes tested, period) is not yet wired into this report, so the county indoor median on the previous page reads Not screened. It populates when the state adapter is completed. The EPA[k] zone above does not depend on it.

SURFACE URANIUM

USGS NURE airborne survey · about 200 mi around TAMPA · 1 km grid · hatched = never flown, or sea



0.4 · 1.0 · 1.6 · 2.2 · 2.7+ ppm eU, light to dark

SOURCE USGS NURE · Goldman and Ellefsen 2020 doi:10.5066/P9YEAFHI · VINTAGE 1970s flights, 2020 model
RETRIEVED 14 Oct 2026 · PROJECTION Web Mercator · north up

Subject property marked as on the zone map

At this address the USGS[k] model gives 0.97 ppm eU, low (under 1.5 ppm; national median 1.6). The figure shows surface uranium within about 200 miles. NURE[k], an airborne gamma-ray survey, flew about 99 percent of the lower 48 in the 1970s and early 1980s on lines 5 to 10 km apart; in 2020 the USGS modelled those lines into a grid of points about 2 km apart, drawn here on a 1 km grid, so the grain reads as continuous texture. Higher eU marks uranium-bearing ground that can feed indoor radon: one input to the EPA[k] county zone, not a prediction for this house. Hatched areas were never flown, or are sea.

READING THIS SECTION


[k] marks a code defined in the codes key at the end of the report.

pCi/L	picocuries per litre of air, the US radon unit; about 37 Bq per cubic metre.
EPA · Zones 1 · 2 · 3	US Environmental Protection Agency county classes by predicted indoor average: 4 pCi/L or more; 2 to 4; under 2.
Short-term	test kit left 2 to 7 days with the house closed (windows shut, no outdoor-air fans).
Sub-slab	depressurization: a pipe and fan under the slab venting soil gas above the roof.
Phase I ESA	Environmental Site Assessment (ASTM E1527): a records review; no air sampling.
NURE · eU · USGS	National Uranium Resource Evaluation, a US Geological Survey airborne gamma-ray survey of the 1970s and early 1980s, lines 5 to 10 km apart over about 99 percent of the lower 48; eU, equivalent uranium, ppm (parts per million): Low under 1.5, Moderate 1.5 to 3.0, Elevated over 3.0.
Rn-222	radon-222, the gas from uranium-238 decaying via radium in soil and rock.
4 pCi/L	EPA action level: fix a home at or above it; consider fixing from 2 pCi/L.
Alpha-track	long-term detector, 90 days or more; averages seasons into an annual estimate.
NRPP · NRSB	National Radon Proficiency Program; National Radon Safety Board: certifiers.
State survey	state radon program aggregate of indoor tests: median, share above 4, homes (n).
Ladder · CBF · EPSG:3857	ticks filled to the rating, Low 1 to Severe 5; Census Cartographic Boundary Files, 1:500k county outlines; Web Mercator projection on the WGS 84 datum.

Source · EPA Radon Zones, 1993 base dataset, screening reference · county geometry Census CBF 500k · basemap © Mapbox, © OpenStreetMap contributors · surface uranium USGS NURE, Goldman and Ellefsen 2020, doi:10.5066/P9YEAFHI, points about 2 km apart, drawn at 1 km · retrieved 14 October 2026 · accuracy county-resolved. A screening output, not a radon measurement; it does not substitute for a direct test of indoor air at this address.

Four wetland features within half a mile, nearest 1,502 ft; none on the parcel

The National Wetlands Inventory maps 4 wetland features within half a mile of the property, in 3 Cowardin systems: estuarine (E), palustrine (P), riverine (R). The nearest, E1UBLx, an estuarine or marine water of 530.6 acres, lies 1,502 ft (458 m) away; none contains the property point.



P palustrine · R riverine · E estuarine · ⊙ subject

SOURCE USFWS NWI map service
RETRIEVED 9 Oct 2026 13:42 PT · VINTAGE 2026-10-09
PROJECTION EPSG:3857 · WGS 84 · Mapbox Satellite · N up

4	1,502 ft	3	none
WETLAND FEATURES	**NEAREST FEATURE**	**COWARDIN SYSTEMS**	**ON THE PARCEL**
NWI polygons within half a mile · 1,457.9 acres mapped	0.28 mi · E1UBLx · estuarine	estuarine, palustrine, riverine	no polygon contains the property point

No mapped polygon reaches the property point; the nearest lies 1,502 ft away. At that distance the parcel is not inside an NWI wetland, but runoff from it may reach one, and local buffer rules can still apply. NWI draws its polygons from imagery at a planning scale, so edges can be off by tens of feet and small or forested wetlands are often missed: the map is a reason to look, not a boundary. Overleaf: each mapped feature decoded, and the permits, federal, state and local.

THE FIVE COWARDIN SYSTEMS

the first letter of every NWI code · 3 present here

Palustrine (P)	freshwater marsh, swamp, bog, small pond	**Lacustrine (L)**	lakes, reservoirs, ponds over 20 acres
Riverine (R)	water within a channel: rivers and creeks	**Estuarine (E)**	tidal, salt to brackish: bays, salt marsh, flats
Marine (M)	open ocean and its exposed coastline		

MAPPED FEATURES WITHIN HALF A MILE, NEAREST FIRST

4 polygons · 1,457.9 acres · distance to the nearest edge

	CODE	NWI TYPE	DECODED	ACRES	DISTANCE
1	E1UBLx	Estuarine and Marine Deepwater	subtidal · unconsolidated bottom · subtidal · excavated	530.6	1,502 ft (458 m)
2	PEM1Fx	Freshwater Emergent Wetland	emergent, persistent · semipermanently flooded · excavated	0.3	2,041 ft (622 m)
3	PEM1Cx	Freshwater Emergent Wetland	emergent, persistent · seasonally flooded · excavated	0.7	2,520 ft (768 m)
4	R2UBH	Riverine	lower perennial · unconsolidated bottom · permanently flooded	926.2	2,589 ft (789 m)

WHAT PROXIMITY MEANS FOR PERMITS

federal, state, local · in the order a project meets them

Section 404	Clean Water Act: placing dredged or fill material in a jurisdictional wetland or stream needs a U.S. Army Corps of Engineers (USACE) permit; grading, roads, culverts and drainage work are the usual triggers.
Nationwide permits	Small, routine fills (under 0.5 acre for a residential project, NWP 29) can use a general nationwide permit with a pre-construction notification; larger work needs an individual permit with public notice.
Section 401	The state certifies that a 404 permit meets its water-quality standards; it can add conditions or refuse, and without it the federal permit cannot issue.
Jurisdictional determination	The Corps decides whether a wetland is a water of the United States (an approved or preliminary JD); since Sackett (2023) only wetlands with a continuous surface connection to a permanent water are federal.
Florida	An Environmental Resource Permit from the state DEP or the water management district covers dredge and fill in state wetlands, beside the Corps' 404 permit (Florida's assumed 404 programme was vacated in 2024).
Local buffers	Counties and cities set building and grading setbacks from wetlands and streams, often 50 to 100 ft, with their own variance paths; they apply whether or not the wetland is federal.

WHAT YOU CAN DO

3 steps · nearest 1,502 ft · sources linked

01 Look at the mapped polygons yourself on the national wetlands mapper; the edge drawn nearest this lot is 1,502 ft away, and walk that ground for standing water and wet-soil plants. fws.gov

02 If a project reaches the mapped edge or wet ground, get a delineation and the Corps' jurisdictional determination before grading or filling. usace.army.mil

03 Florida issues its own environmental resource permit for work in state wetlands, from the department or the water management district, beside the federal one. floridadep.gov


READING THIS SECTION

NWI	USFWS National Wetlands Inventory, mapped from imagery.	Cowardin	USFWS 1979 wetland classification.	Code	System, subsystem, class, subclass, regime, modifier.
E	Estuarine	L	Subtidal	E1	Subtidal
UB	Unconsolidated bottom	x	Excavated	P	Palustrine
EM	Emergent (herbaceous)	EM1	Persistent	F	Semipermanently flooded
C	Seasonally flooded	R	Riverine	R2	Lower perennial
H	Permanently flooded	Jurisdictional	A water the Clean Water Act reaches.	USACE	U.S. Army Corps of Engineers; 404 permits.
JD	Jurisdictional determination, approved or preliminary.	NWP	Nationwide permit: general 404 for small fills.	ESHA	Sensitive habitat area, CA coastal zone.
ft, m, acres	Distance to nearest polygon edge; polygon area.				

USFWS National Wetlands Inventory map service (Wetlands/MapServer), features within 805 m of the property point, retrieved 9 Oct 2026 13:42 PT, query cached 2026-10-09 · basemap Mapbox Satellite, © Mapbox © OpenStreetMap © Maxar · report PLM-20261014151531. A screening output: not a jurisdictional determination or a wetland delineation.

11 schools and four clinics within 1 mi, nearest 0.2 mi

Eight National Register listings within 1 mi, the nearest 70 ft E. Peter O Knight, 2.5 mi S, is an AFFF-capable airport; its 3 mi PFAS screening radius reaches the property.



subject property · school · clinic · National Register listing · AFFF-capable airport · seaplane base · heliport · 1 mi, 5 mi from the subject · 3 mi PFAS screening radius · numbers: ledger row

OSM via Overpass · FAA NTAD aviation facilities · NPS National Register · all retrieved 14 Oct 2026
Vintage as published at retrieval, OSM live · Web Mercator, north up · 1 mi ring drawn; 5 mi ring beyond the plate
Basemap Mapbox light with paper overrides, © Mapbox © OpenStreetMap contributors

11	4	8	1
SCHOOLS, DAYCARES	**HOSPITALS, CLINICS**	**REGISTER LISTINGS**	**AFFF AIRPORTS**
within 1 mi · nearest 0.46 mi SE	within 1 mi · nearest 0.23 mi N	within 1 mi · nearest 70 ft E	within 5 mi · nearest 2.5 mi S · 3 mi radius reaches the property

RECEPTOR LEDGER, NUMBERED ON THE PLATE — 6 of 32 marks · nearest first within each kind

#	KIND	NAME	SOURCE	DISTANCE	BEARING
1	clinic	unnamed clinic	OSM clinic	0.23 mi	N
2	school	Sam Rampello Downtown Partnership School	OSM school	0.46 mi	SE
3	school	Tampa Preparatory School	OSM school	0.47 mi	W
4	Register listing	Kress, S.H., and Co. Building	NRHP 83001424 · 1983	70 ft	E
5	Register listing	Tampa Theater and Office Building	NRHP 78000945 · 1978	340 ft	SE
6	AFFF airport	Peter O Knight	FAA A · 3 mi arc reaches	2.53 mi	S

and 26 more on the plate without a number: 12 schools or clinics within 1 mi, 6 listings within 1 mi and 8 aerodromes within 5 mi

Within 1 mile of the property the map places 11 schools (schoolhouse and pram marks), 4 clinics (cross marks, solid for a hospital, hollow for a clinic), 8 National Register listings (columned-building marks), each numbered to the receptor ledger. The airplane marks PETER O KNIGHT, 2.5 mi S, an airport that may have used AFFF firefighting foam; the dashed amber arc is its 3-mile PFAS screening radius, which reaches the property. The small grey marks (H in a ring for a heliport, a hollow plane for an airfield) are 7 heliports and 1 seaplane base within 5 miles; they carry no PFAS screening radius.

Why it matters: a school, daycare, hospital or clinic is a sensitive receptor; near a regulated facility it tightens state cleanup targets and lender questions. A Register listing or district can bring Section 106 review to work with a federal permit or federal money. An AFFF-capable airport within 3 mi is the screening trigger for PFAS in groundwater: the foam was sprayed for decades in runway fire drills.

What the map cannot show: OpenStreetMap is a volunteer map, so a school missing from it is missing here. State daycare licence lists are not queried, so licensed home daycares will be absent. The FAA list includes every rooftop helipad; only runways carry a screening radius. Register listings are points at the listed address, not district outlines.

PFAS SCREENING

Peter O Knight lies 2.5 mi from the property, inside the 3 mi AFFF screening radius; groundwater PFAS sampling is the usual next step where the property has a well or a shallow aquifer.

WHAT EACH MARK MEANS

glyphs as drawn on the plate

School	Primary or secondary school tagged in OpenStreetMap; searched within 1 mi. A sensitive receptor.	**Clinic**	Clinic or urgent care tagged in OpenStreetMap; searched within 1 mi. Hollow cross.
National Register listing	A building, site, structure or object on the National Register of Historic Places; within 1 mi.	**AFFF-capable airport**	FAA type A runway airport, where AFFF foam was used; within 5 mi, with its dashed amber 3 mi arc.
Seaplane base	FAA type S seaplane base; grey when the PFAS score does not treat it as a runway. Within 5 mi.	**Heliport**	FAA type H helipad, often on a hospital or office roof; no runway and no screening radius.
Subject	The property: ink ring, white core, the same on every map in this report.	**1 mi, 5 mi rings**	Search radii from the subject: 1 mi for receptors and listings, 5 mi for aviation facilities.
3 mi arc	PFAS screening radius around each AFFF-capable airport; the finding is whether it reaches the subject.		

WHAT YOU CAN DO

4 steps · foam-capable airport 2.53 mi · sources linked

01 On a private or shallow well, test for the two foam chemicals the federal rule limits to 4 parts per trillion. epa.gov

02 On city water, read the utility's annual water quality report; since 2024 it must carry PFAS results. epa.gov

03 If a test finds them, a tap or under-sink filter certified for PFAS is the agency's fix; change cartridges on schedule. epa.gov

04 A Register listing is within a mile: federally permitted or funded work gets a Section 106 review; ask the state historic office early. achp.gov

READING THIS SECTION


[k] marks a code defined in the codes key at the end of the report.

AFFF-capable	FAA type A or S, a runway facility where AFFF was plausibly used; only these are scored for PFAS.	3 mi radius	Screening distance around an AFFF-capable airport; inside it, ask about groundwater PFAS.
Receptor	A place contamination could reach; schools, daycares, hospitals and clinics are the sensitive ones.	FAA site types	A airport · H heliport · S seaplane base · B balloonport · G gliderport · U ultralight field.
Daycare	An OSM feature tagged kindergarten or childcare; state licence lists are not queried in this edition.	1 mi, 5 mi	Straight-line search radii from the subject: receptors and listings 1 mi, aviation facilities 5 mi.
Bearing	Compass direction from the subject to the mark, in eight points (N, NE, E, SE, S, SW, W, NW).		

OpenStreetMap via Overpass, retrieved 14 Oct 2026, live data, status ok · FAA NTAD aviation facilities (BTS), 14 Oct 2026 · NPS National Register, 14 Oct 2026, both as published at retrieval · basemap © Mapbox © OpenStreetMap · PLM-20261014151531

Good air on 278 of 359 days in 2025

The nearest EPA[k] monitor, Munro Street (Near-Road) (0.7 mi NW), reported 359 days in 2025: 278 Good, 81 Moderate, 0 worse. Annual mean 7.3 µg/m³[k] against a standard of 9; worst day 18 µg/m³ on 5 June.



AT THE TIME OF THIS REPORT

43 AQI[k]

Good

O3[k] · 46.0 ppb

Observed **14 Oct 2026, 5:00 pm EDT** (AirNow[k])
Monitor: MUNRO STREET, 0.7 mi from the property
One hour's reading; the finding rests on the full-year record.

— 2025 monthly mean AQI —— 2024 and 2023
lowest to highest day in the month
y: AQI (PM2.5[k] or ozone, the higher) · x: months · county monitors

SOURCE EPA AQS[k] daily, 88101 PM2.5, 44201 ozone
SITE 120570113 Munro Street (Near-Road), 0.7 mi NW
OZONE 120571035 Davis Island, 1.5 mi S
RETRIEVED 14 Oct 2026 · DATA 2023 to 2025

7.3 µg/m³	0 days	65 ppb	1 days
ANNUAL MEAN PM2.5, 2025 micrograms of fine particles per cubic metre; standard 9 as a three-year mean (here 7.6)	**DAILY LIMIT EXCEEDED** days above 35 µg/m³; met when the 98th-percentile day is 35 or under (here 14)	**OZONE DESIGN VALUE** parts per billion; 4th-highest daily 8-hour peak, 2023 to 2025 mean; standard 70	**EXCEEDANCE DAYS, 2025** days over AQI 100 (unhealthy for sensitive groups or worse) for PM2.5 or ozone

Munro Street (Near-Road) is the EPA monitor nearest the property, 0.7 mi to the NW. In 2025 it reported a certified 24-hour PM2.5 value on 359 of 365 days: 278 Good (9.0 µg/m³ or less), 81 Moderate (9.1 to 35.4) and 0 worse; the highest was 18 µg/m³ on 5 Jun 2025. Both PM2.5 standards (NAAQS[k]) are three-year averages, tested in the table overleaf: the monitor meets both PM2.5 standards, and ozone's 65 ppb design value is under the 70 ppb standard. EPA's attainment designations cover whole areas, not one monitor.

WHAT HAPPENED: DAYS OVER 35.4 µg/m³, 2023 TO 2025


2 to 5 October 2023: four days, 1 over 35.4; peak 37.7 µg/m³ (AQI 107, Unhealthy for sensitive groups) on 3 October. Cause not attributed; no mapped fire of 100 acres or more within 300 km in that window.

31 December 2023 to 1 January 2024: two days, 1 over 35.4; peak 44.1 µg/m³ (AQI 122, Unhealthy for sensitive groups) on 1 January. Cause not attributed; no mapped fire of 100 acres or more within 300 km in that window. The dates coincide with New Year's Eve fireworks, a common source of a one-night particle spike.

fires within 300 km, three days either side

A YEAR OF AIR, ONE SQUARE PER DAY: 2025

EPA[k] AQS[k] 120570113 · Munro Street (Near-Road) · 24-hour PM2.5[k]



dot: Moderate · colour: AQI band, key below 47 value printed on days over 35.4 · 24-hour means, µg/m³ no reading: 6 days

SIX AQI[k] BANDS, 2025 DAY COUNTS

2024 breakpoints

BAND	DAYS	AQI	PM2.5 µg/m³[k]
Good	278	0 to 50	0 to 9.0
Moderate	81	51 to 100	9.1 to 35.4
Unhealthy, sensitive groups	0	101 to 150	35.5 to 55.4
Unhealthy	0	151 to 200	55.5 to 125.4
Very unhealthy	0	201 to 300	125.5 to 225.4
Hazardous	0	301 to 500	225.5 and up
No reading	6	–	–

THE THREE-YEAR TEST

standards are three-year averages

YEAR	MEAN µg/m³	98TH PCT	DAYS >35	O_3[k] PPB	COUNTY
2023	8.2	16.8	1	64	3
2024	7.4	15.1	1	68	4
2025	7.3	13.9	0	63	2
Standard	**9.0**	**35**	–	**70**	–

O_3: 4th-highest daily 8-hour peak, Davis Island. County: days over AQI 100 at any Hillsborough County monitor. Days >35: over the daily standard here.

The year before, 2024, Munro Street (Near-Road) reported 351 days: 285 Good, 65 Moderate, 1 worse; worst day 44 µg/m³ on 1 Jan 2024. PM2.5 concentrations tend to peak in winter when temperature inversions trap wood smoke and heating emissions near ground level. Nothing here triggers a permit or disclosure; the readings matter most for occupants sensitive to fine particles.

WHAT YOU CAN DO

3 steps · mean 7.4 µg/m³ · 2 days over 100 in 2025 · sources linked

01 Check the forecast and the fire-and-smoke map on a bad day and sign up for the county's alerts; the 100 line is where sensitive people cut outdoor effort. fire.airnow.gov

02 On a smoke day close the windows and run the central fan on recirculate with a filter rated 13 or higher on the furnace-filter scale; most systems take one. epa.gov

03 A portable air cleaner sized for the bedroom makes one clean room; the agency's guide says what size to buy and to avoid ozone generators. epa.gov

READING THIS SECTION

[k] marks a code defined in the codes key at the end of the report.

AQI	Air Quality Index, 0 to 500: 50 tops Good, 100 marks each pollutant's short-term standard; the six bands in the table above.
98th pct	Value that 98 percent of the year's days fall at or under.
NIFC, MTBS	National Interagency Fire Center perimeters (WFIGS, with discovery and containment dates); Monitoring Trends in Burn Severity burned areas (ignition dates).
Site id	AQS id: state (2), county (3), site (4) digits.
PM2.5, O_3	Fine particles under 2.5 micrometres (AQS code 88101); ground-level ozone (44201).
Episode	A day over 35.4 µg/m³ with its adjacent days over 9.0; fires of 100 acres or more within 300 km (186 mi), three days either side, named by size.
AQS, AirNow	EPA's certified monitor archive; EPA's hourly real-time feed, uncertified.

EPA AQS daily API (data 2023 to 2025), AirNow, NIFC WFIGS and history, MTBS: retrieved 14 Oct 2026 · PLM-20261014151531

Six hurricanes within 50 mi since 1950; nearest Irma 2017, Category 1, 20 mi

31 cyclones within 50 mi since 1950, 6 as hurricanes when nearest; 77 tornado paths within 10 mi, nearest 0.6 mi in 1968; FEMA[k] rates the tract Relatively High for hurricane and tornado.



subject · 10 and 50 mi · closest approach, labelled
hurricane track, weight = category when nearest
tropical storm · depression or remnant
tornado path, weight = EF · land (Natural Earth)
water · north up

NOAA HURDAT2 Atlantic 1851 to 2025, Pacific 1949 to 2025 released 23 Sep 2026 and 29 Sep 2026 · fetched 13 Oct 2026
SPC paths 1950 to 2025 (28 Apr 2026), fetched 13 Oct 2026
FEMA NRI December 2025 · tract 12057005101 · 14 Oct 2026

6	0.6 mi	*High*	$1.37M
HURRICANES WITHIN 50 MI	**NEAREST TORNADO TRACK**	**NRI WIND RATING**	**EXPECTED ANNUAL LOSS**
when nearest; 0 at Category 3 or more	1968 · F1 · E · 77 paths within 10 mi, 325 within 25 mi	hurricane and tornado Relatively High; strong wind Relatively Low	a year, hurricane, this tract (NRI); see annex for ASCE 7

What the history says. NOAA[k]'s best track is each storm's centre every six hours: the 31 tracks are centres that passed, not winds that blew here; a hurricane's damaging winds reach 25 to 50 mi out. Nearest at hurricane strength: Irma 2017, Category 1, 20 mi east-northeast; strongest: Milton 2024, Category 2 at 28 mi; 14 more at hurricane strength before 1950, the nearest in 1946. Tornadoes: 325 paths within 25 mi since 1950; the strongest, F4 on 1966-04-04, ran 136 mi, 3.4 mi NNW of the subject, and hurt 530, killing 11.

What the building code assumes here. Florida's statewide code (2002) takes its wind loads from ASCE 7[k]: a design wind speed for the site and, along the coast, a wind-borne debris region where glazed openings must be impact-rated or shuttered and roof decks strapped. A house permitted before 2002 was built to the county code of its day: the year built and the roof's permit date say more than the address.

Strongest to pass: Milton 2024, Category 2, 28 mi to the south-southeast

Storms within 50 mi since 1950, nearest first; then the tornado paths within 10 mi.

STORMS WITHIN 50 MI SINCE 1950 6 hurricanes · 11 tropical storms · wind in mph, one-minute sustained

STORM	NEAREST ON	CATEGORY	WIND	PEAK	MI	BEARING
Irma	11 Sep 2017	Cat 1	77	178	20	ENE
Easy	6 Sep 1950	Cat 1	76	121	25	NNE
Milton	10 Oct 2024	Cat 2	105	178	28	SSE
Donna	11 Sep 1960	Cat 1	85	144	41	E
Gladys	19 Oct 1968	Cat 2	98	98	45	NW
Charley	14 Aug 2004	Cat 2	104	150	46	ESE
Unnamed	18 Jun 1959	TS	46	86	12	NNW
Frances	6 Sep 2004	TS	63	144	14	NNE
Jeanne	26 Sep 2004	TS	67	121	24	NE

8 more tropical storms beyond 24 mi not listed; 14 depressions or remnants (nearest 1987, 4.1 mi NW) drawn dashed, not listed.

TORNADO PATHS WITHIN 10 MI 77 since 1950 · n/r = not recorded

DATE	SCALE	MI	BEARING	LEN	YD	HURT
1968-11-09	F1	0.6	E	69.3	10	3
1971-08-02	F1	0.6	W	0.3	20	none
2013-02-26	EF0	0.9	SE	0.7	50	none
1968-11-11	F1	1.3	NNW	57.2	10	none
1971-03-03	F0	1.3	W	0.3	10	none
1971-10-17	F1	1.4	NNE	0.3	10	none
1971-03-03	F0	1.5	NNW	0.1	10	none

70 more within 10 mi, not listed; 325 within 25 mi: 184 EF0, 102 EF1, 30 EF2, 2 EF3, 2 EF4, 5 unrated. Length in mi, width in yards, as surveyed.

What an insurer asks. Florida insurers price wind by the house, not the street. A wind mitigation inspection (form OIR-B1-1802, valid five years) records the roof's shape, nailing, straps, water barrier and opening protection; s. 627.0629 makes each a premium discount. A 4-point inspection is asked for on homes over about twenty years old. Expect a hurricane deductible of 2 to 10 percent of the dwelling limit, and ask whether the carrier is Citizens, the state's insurer of last resort.

History is the area's, not the house's. The tracks and the tract rating describe the ground the house stands on: how often storms pass and what they cost the neighbourhood. What this house does in the next one depends on its roof, its straps and its openings, which only an inspector can see.

WHAT YOU CAN DO

1. Find your evacuation zone and nearest shelter before the season; zones follow surge, not distance from the water. floridadisaster.org/knowyourzone
2. Order a wind mitigation inspection (form OIR-B1-1802): roof deck, straps, shape and opening protection, each a discount by law. floir.com
3. Protect every opening with impact-rated shutters or glazing; the garage door first, it fails first. ready.gov/hurricanes
4. When the roof is replaced ask for a sealed deck and straps; the Fortified Roof standard is the one insurers recognise. fortifiedhome.org
5. Pick a tornado room now: an interior room on the lowest floor, or a safe room built to FEMA P-320. fema.gov/safe-rooms

READING THIS SECTION

[k] marks a code defined in the codes key at the end of the report.

HURDAT2 NOAA National Hurricane Center (NHC) best track: every Atlantic (1851 on) and northeast Pacific (1949 on) cyclone's centre, wind and status every six hours. **SPC** NOAA Storm Prediction Center; its tornado database runs from 1950 with a start and an end point for each tornado. **Tornado path** The straight line from the SPC start point to the end point; a record with no end point is drawn as a dot. **NRI** FEMA National Risk Index: a census-tract rating for 18 hazards, Very Low to Very High, from expected annual loss, social vulnerability and resilience. **Expected annual loss** NRI's average yearly dollar loss in the tract from one hazard; the tract's exposure, not this building's. **Saffir-Simpson** Hurricane categories by one-minute sustained wind: 1 is 74 to 95 mph, 2 is 96 to 110, 3 is 111 to 129, 4 is 130 to 156, 5 is 157 or more; TS a tropical storm, 39 to 73; TD a depression, under 39. **When nearest** The category where the track came nearest the subject, from the wind interpolated between the fixes either side. **EF scale** Enhanced Fujita tornado damage scale since 2007: EF0 65 to 85 mph, EF1 86 to 110, EF2 111 to 135, EF3 136 to 165, EF4 166 to 200, EF5 over 200; F0 to F5 is the older Fujita scale, printed before 2007. **ASCE 7** The load standard the building codes adopt; its wind-speed maps are served only through interactive tools with no public data feed, so the NRI loss stands in. **Wind-borne debris region** ASCE 7 and the Florida Building Code: within 1 mi of the coast where the design wind speed is 130 mph or more, or anywhere 140 mph or more; glazed openings must be impact-rated or shuttered. **Wind mitigation inspection** Florida's uniform form OIR-B1-1802 recording the features that resist wind; valid five years; each feature earns a discount under s. 627.0629. **4-point inspection** An insurer's check of roof, electrical, plumbing and heating and cooling on older homes; not a wind inspection.

NOAA NHC HURDAT2 Atlantic (23 Sep 2026) and northeast Pacific (29 Sep 2026) best track · NOAA SPC tornado paths 1950 to 2025 (28 Apr 2026) · fetched 13 Oct 2026 · FEMA NRI December 2025, tract 12057005101, retrieved 14 Oct 2026 · Natural Earth 10 m · PLM-20261014151531

24 sources, all returned; composite 2.3 of 10

How the rating was made, where every number came from, and what the integrity word means.

The address was geocoded by the US Census Geocoder (Census exact match (TIGER[k] line 104530091)) to 27.95098° N, 82.45933° W. Around that point 24 public datasets were queried, each at the screening distance its section states: two miles for regulated facilities and wells, five miles for airports, five kilometres for pipelines, 30 miles for fire perimeters, two kilometres for listed species, 500 metres for easements and historic listings, one mile for schools and clinics. 24 of 24 returned.

Each of the sixteen sections is scored on a four-step scale (0 to 3) from its federal source record, shown on a 0 to 10 display scale, and given a fixed weight; the weights sum to 100% and the weighted sum is the composite, 2.3 here. A section marked not assessed carries no score and no weight.

The composite falls into one of four bands: Low below 2.1, Moderate 2.1 to 4.0, Elevated 4.1 to 6.5, High 6.6 and above. Severe is not a band but a trigger, a Superfund (NPL[k]) site within 0.5 mi, which overrides the composite; none applies here.

Checks: **passed**, one of three words keyed below; a retrieval and consistency check, not a verification of the public records. Numeric reconciliation means every figure the prose prints was checked against the record it came from before the report was issued; a mismatch sets the status to Failed.

Figure pages were suppressed for seismic, endangered species: nothing to draw at this address, the screening result stands in the findings ledger.

Checks: passed THIS REPORT
every core source answered, every figure reconciled to its record, every cross-check passed; a retrieval and consistency check, not a verification of the underlying public records

Checks: passed with gaps
complete and honest, but a source was not available or a check could not run; the gaps are named in the sources ledger

Checks: failed
a check found a contradiction; do not rely on the report

16 SECTIONS: SCORE, WEIGHT, LEVEL

composite 2.3 of 10 · Moderate

SECTION	SCORE (0 TO 10)	WEIGHT	LEVEL
EPA / RCRA facilities	3.3	18%	Moderate
Storage tanks (UST / LUST)	0.0	15%	Low
Flood zone	0.0	12%	Low
Wetlands	6.7	3%	Elevated
Air quality	0.0	5%	Low
Geology and soil	10.0	7%	High
Seismic hazard	0.0	8%	Low
Wildfire	3.3	4%	Moderate
Endangered species	0.0	6%	Low
Historic register	3.3	3%	Moderate
Coastal zone	6.7	2%	Elevated
Conservation easements	0.0	4%	Low
PFAS (airports)	10.0	4%	High
Pipelines	0.0	4%	Low
Landslides	0.0	3%	Low
Radon	3.3	2%	Moderate
Composite	**2.3**	**100%**	Moderate

REGULATED FACILITIES, THE ONE WEIGHTED SECTION

program weight × distance factor, summed

Regulated facilities is the only section built from a weighted sum rather than a single reading. Each facility within two miles contributes its program weight (Superfund 3.0, RCRA[k] treatment, storage or disposal 2.5, RCRA large-quantity generator 2.0, TRI[k] reporter 1.5, Clean Water Act discharger 1.3, small generators 1.2 and 0.8, Clean Air Act registration only 0.5), plus 1.0 for significant non-compliance (SNC[k]) or 0.5 for an active violation, multiplied by a distance factor (1.0 to 0.25 mi; 0.7 to 0.5 mi; 0.4 to 1.0 mi; 0.15 beyond). The sum maps to the four-step scale at 2.0 / 8.0 / 25.0.

Permit volume alone cannot lift the section past Moderate: Elevated and High require weight from Tier I and II facilities (Superfund, RCRA TSD[k] or LQG[k], TRI, non-compliance).

For this property: 708 facilities within two miles, 7 of them Tier I or II. Raw weighted score 333.8 (all facilities), 2.5 from Tier I and II alone. Band from all facilities 3 of 3; from Tier I and II 1 of 3; section score used 1 of 3.

DATA SOURCES · STATUS AT RETRIEVAL · RETRIEVED

24 of 24 returned

SOURCE	STATUS	RETRIEVED
US Census Geocoder	returned	14 Oct 2026
EPA ECHO	returned	14 Oct 2026
EPA ECHO UST/ LUST	returned	14 Oct 2026
EPA Envirofacts TRI	returned	14 Oct 2026
AirNow API	returned	14 Oct 2026
EPA AQS	returned	no date
EPA ECHO SDWIS	returned	9 Oct 2026
FEMA NFHL	returned	13 Oct 2026
USFWS NWI	returned	9 Oct 2026
USGS 3DEP	returned	9 Oct 2026
USGS Earthquake Hazards	returned	9 Oct 2026
EPA Radon Zones	returned	9 Oct 2026
Macrostrat API	returned	9 Oct 2026
USFS Wildfire Hazard	returned	14 Oct 2026
USFWS ECOS	returned	14 Oct 2026
NPS National Register	returned	14 Oct 2026
NOAA Coastal Zone	returned	14 Oct 2026
NCED / PAD-US	returned	14 Oct 2026
FAA Airport Data	returned	14 Oct 2026
EIA Natural Gas Pipelines	returned	9 Oct 2026
EIA Hazardous Liquid Pipelines	returned	9 Oct 2026
USGS Landslide Hazards	returned	9 Oct 2026
OpenStreetMap Overpass	returned	no date
USGWD Well Database	returned	no date

Report generated 14 Oct 2026, 3:15 PM PT. Each source carries its own retrieved date; a date earlier than the report's is a cached source record reused unchanged. No date: the source answered without a timestamp. Returned = answered and reconciled. Partial = answered with gaps; not returned = no answer, and the section it feeds is marked not assessed.

WHAT THIS REPORT IS, AND IS NOT

important legal notice

This Groundsheet environmental pre-screen report ("Report") is produced by Groundsheet, a product of Ashcroft and Thorn, and is intended solely as a preliminary informational screening tool. It is **not** a Phase I Environmental Site Assessment as defined by ASTM E1527-21[k] and does **not** satisfy the All Appropriate Inquiries (AAI[k]) standard under 40 CFR[k] Part 312. It does not provide CERCLA[k] liability protection and should not substitute for a Phase I ESA[k] conducted by a qualified environmental professional.

This Report does not provide: CERCLA liability protection or an innocent landowner defense; a professional opinion from a qualified Environmental Professional (EP[k]); site inspection, interviews, or historical records review; state or local database searches beyond federal sources; or any guarantee of completeness or accuracy of the underlying federal databases.

Data is sourced from publicly available federal databases (EPA[k], FEMA[k], USFWS[k], USGS[k] and the others listed above); accuracy depends on source database completeness and currency. Risk scores and ratings are generated algorithmically from that data, using a weighted algorithm based on proximity, severity and regulatory status, and should be read as relative screening indicators only, not as definitive environmental assessments. Scores may not reflect current conditions, recent contamination events, or state-level regulatory actions not captured in federal databases. If concerns are identified, engage a qualified environmental professional for appropriate due diligence.

By using this Report, you acknowledge that: (a) it is not a substitute for professional environmental due diligence; (b) Ashcroft and Thorn and its affiliates assume no liability for decisions made based on it; (c) you should engage a qualified environmental professional before making any acquisition, lending, or development decision based on environmental risk; (d) data sources are subject to lag, omission, and error beyond our control.

For questions about this Report, contact hello@getgroundsheet.com. © 2026 Groundsheet. All rights reserved.

READING THIS SECTION

[k] marks a code defined in the codes key, pages 36 to 40.

Tier I, II	Groundsheet facility tiers: I is Superfund (NPL), leaking tank, RCRA treatment-storage-disposal (TSD) or significant non-compliance (SNC); II is a RCRA large (LQG) or small quantity generator or TRI reporter.
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act, the Superfund law whose liability defenses depend on a proper Phase I ESA under ASTM E1527-21 and AAI (40 CFR Part 312).

Provenance: report PLM-20261014151531 · 24 sources · generated October 14, 2026 (PDT) · every code printed here is keyed at the end of this report

9 chemicals named in this report

Every chemical surfaced from federal Toxics Release Inventory (TRI[k]) filings, named as EPA[k] lists it, with a PubChem[k] reference you can check; where PubChem has no description, the entry says so.


Benzo[g,h,i]perylene CAS 191-24-2



Benzo[ghi]perylene is an ortho- and peri-fused polycyclic arene.

Source: PubChem CID 9117 · pubchem.ncbi.nlm.nih.gov/compound/9117

Ethylbenzene CAS 100-41-4



Ethylbenzene can cause cancer according to The World Health Organization's International Agency for Research on Cancer (IARC[k]).

Source: PubChem CID 7500 · pubchem.ncbi.nlm.nih.gov/compound/7500


Lead compounds Pb TRI N420

This is a chemical category, not a single compound; no single-compound reference applies.

Mercury compounds Hg TRI N458

This is a chemical category, not a single compound; no single-compound reference applies.


n-Butyl alcohol CAS 71-36-3



Butan-1-ol is a primary alcohol that is butane in which a hydrogen of one of the methyl groups is substituted by a hydroxy group. It it produced in small amounts in humans by the gut microbes. It has a role as a protic solvent, a mouse metabolite and a human metabolite. It is a primary alcohol, a short-chain primary fatty alcohol and an alkyl alcohol.

Source: PubChem CID 263 · pubchem.ncbi.nlm.nih.gov/compound/263

n-Hexane CAS 110-54-3




n-Hexane can cause male reproductive toxicity according to an independent committee of scientific and health experts.

Source: PubChem CID 8058 · pubchem.ncbi.nlm.nih.gov/compound/8058

Polycyclic aromatic compounds TRI N590

This is a chemical category, not a single compound; no single-compound reference applies.

Toluene CAS 108-88-3



Toluene can cause developmental toxicity according to an independent committee of scientific and health experts. It can cause female reproductive toxicity according to California Labor Code.

Source: PubChem CID 1140 · pubchem.ncbi.nlm.nih.gov/compound/1140

Xylene (mixed isomers) CAS 1330-20-7

This is a chemical category, not a single compound; no single-compound reference applies.

READING THIS SECTION

[k] marks a code defined in the codes key, pages 36 to 40.

CAS	Chemical Abstracts Service registry number: one identifier per substance, used worldwide; it links to the PubChem record.
TRI N-code	EPA Toxics Release Inventory category code for a group of related compounds reported together (N420 lead compounds, N458 mercury compounds).
Pb, Hg	The element symbol printed beside a metal compound category: the metal the category is defined by (lead, mercury, chromium and so on).

Descriptions are reproduced verbatim from their cited sources, including any errors present in the original; follow the source link to verify. Provenance: report PLM-20261014151531 · 9 chemicals surfaced by the facility section · names from EPA's TRI chemical list · descriptions and 2-D structures from PubChem (U.S. National Library of Medicine), retrieved at generation · generated October 14, 2026 (PDT)

Every code this report prints, one line each

Every code this report prints, under thirteen headings, alphabetical within each; the RCRA generator designations read as one block under RCRA. A small raised k after a code in the text (RCRA[k]) means it is defined here. Each section page also keys the codes it uses in its own annex.

CODES KEY · EVERY CODE PRINTED IN THIS REPORT, ONE HUNDRED AND SEVENTY-SEVEN ENTRIES UNDER 13 HEADINGS

[k] after a code elsewhere in this report marks a code defined here.

REGULATORY PROGRAMMES

AAI	All Appropriate Inquiries, 40 CFR Part 312: the standard a Phase I ESA must meet.
ASTM E1527-21	Standard practice for Phase I Environmental Site Assessments.
CAA	Clean Air Act; a CAA registration alone makes a Tier III facility.
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act: Superfund.
CFR	Code of Federal Regulations, cited as title and part (40 CFR 312).
CWA	Clean Water Act: discharge permits and the Section 404 wetlands permit.
CZMA	Coastal Zone Management Act: state review of development in the coastal zone.
ECHO	EPA Enforcement and Compliance History Online, the regulated-facility record.
EPA	US Environmental Protection Agency.
ESA	Endangered Species Act.
FR	Federal Register, cited as volume and page (78 FR 8746); where listings are published.
NHPA	National Historic Preservation Act.
NPL	National Priorities List: the Superfund list of the most serious contaminated sites.
Phase I ESA	Phase I Environmental Site Assessment (ASTM E1527-21); this report is not one.
RCRA	Resource Conservation and Recovery Act, the federal hazardous-waste programme; each handler carries one designation (LQG, SQG, VSQG or TSD), set by the waste it generates in a month or whether it treats others' waste.
└ LQG	Large quantity generator: 1,000 kg (2,200 lb) or more a month, or over 1 kg acutely hazardous; strictest generator rules; Tier II. Printed RCRA-LQG.
└ SQG	Small quantity generator: 100 to 1,000 kg a month; Tier II. Printed RCRA-SQG.
└ VSQG	Very small quantity generator: under 100 kg a month (formerly CESQG); Tier III. Printed RCRA-VSQG.
└ TSD	Treatment, storage or disposal facility: permitted to take others' hazardous waste; Tier I. Printed RCRA-TSD.
└ RCRAInfo	EPA's RCRA handler database, the source of each designation.
REC	Recognized Environmental Condition: the Phase I ESA finding of a likely release.
RY2024	TRI reporting year 2024, the latest release filings available at generation.
SDWA	Safe Drinking Water Act.
TRI	Toxics Release Inventory: annual chemical-release reporting by larger facilities.
VCP	Voluntary cleanup programme: a state scheme for owner-led cleanup to agreed standards.

FACILITY TIERS AND DESIGNATIONS

EP	Environmental Professional, the qualified person a Phase I ESA is conducted under.
FRS	EPA Facility Registry Service; a plain FRS registration carries no programme flag (Tier IV).
LUST	Leaking underground storage tank.
SDWIS	EPA Safe Drinking Water Information System, the public water system record.
SNC	Significant non-compliance with an environmental permit.
Tier I	Groundsheet tier: Superfund (NPL), leaking tank, RCRA TSD, or significant non-compliance.
Tier II	Groundsheet tier: RCRA large or small quantity generator, or TRI reporter.

Codes key *continued*

FACILITY TIERS AND DESIGNATIONS continued

Tier III	Groundsheet tier: very small generator, CAA or CWA permit, water system, registered tank.
Tier IV	Groundsheet tier: registered with EPA, no actionable programme flag.
UST	Underground storage tank, registered with the state or EPA.

FLOOD AND TERRAIN

3DEP	USGS 3D Elevation Program, the national elevation model under the terrain view.
BFE	Base Flood Elevation: the 1-percent-annual-chance flood's water surface, in feet.
FEMA	Federal Emergency Management Agency, publisher of the flood maps.
FIRM	Flood Insurance Rate Map: the FEMA panel that fixes an area's zones and BFEs.
NAVD 88	North American Vertical Datum of 1988, the sea-level reference for every elevation here.
NFHL	FEMA National Flood Hazard Layer, the digital flood map.
SFHA	Special Flood Hazard Area, the 1-percent floodplain; insurance mandatory on federally backed loans.
Zone A, AE	FEMA 1-percent-annual-chance floodplain (100-year); AE has a published BFE.
Zone AH, AO	FEMA shallow flooding or ponding, 1 to 3 ft deep.
Zone V, VE	FEMA coastal high-risk area with wave action.
Zone X	FEMA minimal risk (unshaded) or moderate, the 500-year floodplain (shaded).

WILDFIRE

MTBS	Monitoring Trends in Burn Severity: USGS and USFS satellite mapping of burned area and severity.
NIFC	National Interagency Fire Center, the historical fire perimeter record.
USFS	US Forest Service.
WFIGS	Wildland Fire Interagency Geospatial Services, the NIFC perimeter feed.
WHP	USFS Wildfire Hazard Potential, a five-class national raster (very low to very high).

GEOLOGY AND SEISMIC

ASCE 7	The structural load standard that defines the seismic design values printed here.
B1, B2, B3	USGS karst exposure classes: B1 carbonate buried under less than 50 ft of cover, B2 under 50 to 200 ft, B3 under more than 200 ft; E is exposed at the surface.
CGS	California Geological Survey, publisher of the state geologic map.
Cover-collapse	A sinkhole that opens abruptly when the soil cover falls into a cavity in the rock below; the damaging kind.
Cover-subsidence	A sinkhole that forms slowly as sand cover settles into the rock; gradual, rarely sudden.
FGS	Florida Geological Survey, keeper of the state's subsidence incident reports (sinkhole reports filed by the public and insurers).
GPM	Gallons per minute, the well yield unit.
HydroShare	The CUAHSI (university water-science consortium) data repository that publishes USGWD.
Karst	Terrain on soluble rock (limestone, dolomite, gypsum) where water has opened cavities; sinkholes, springs and fast groundwater movement follow.
Karst	Soluble rock (limestone, dolomite, gypsum) prone to sinkholes and caves.
Ma	Million years ago, the age unit on the geologic column.
OFR 2014-1156	USGS Open-File Report 2014-1156, the national karst map compilation (Weary and Doctor 2014) that draws the carbonate and pseudokarst polygons.
PGA	Peak ground acceleration, in g (share of gravity).
S1	Mapped spectral acceleration at a 1-second period on site class BC, in g.
SD1	Design spectral acceleration at 1 second (ASCE 7), in g; governs taller buildings.
SDC	Seismic Design Category, ASCE 7: A (lowest) to E/F, from design accelerations and soil.
SDS	Design spectral acceleration at short periods (ASCE 7), in g; governs low, stiff buildings.

Codes key *continued*

GEOLOGY AND SEISMIC continued

SIR	Subsidence incident report: one filed sinkhole or ground-collapse event in the FGS register, with its date, size and rate as reported.
Site class BC	ASCE 7 default ground class, soft rock to very dense soil (VS30 about 760 m/s), assumed without a soil survey.
SS	Mapped spectral acceleration at short period (0.2 s) on site class BC, in g.
USGS	US Geological Survey.
USGWD	United States Groundwater Well Database, 14.2 million well records.
VS30	Average shear-wave velocity in the top 30 m of ground, in m/s; sets the site class.

RADON

4 pCi/L	EPA action level: fix a home at or above it; consider fixing from 2 pCi/L.
CBF	Census cartographic boundary file, the 1:500,000 county outlines on the radon map.
eU	Equivalent uranium, in ppm: the NURE measure from gamma radiation.
NRPP	National Radon Proficiency Program, a certifier of radon testers and mitigators.
NRSB	National Radon Safety Board, the other national certifier.
NURE	USGS National Uranium Resource Evaluation, the 1970s airborne survey behind the surface-uranium map.
pCi/L	Picocuries per litre of air, the US radon unit; about 37 becquerels per cubic metre.
Radon zones	EPA county zones: 1 predicted above 4 pCi/L indoors, 2 between 2 and 4, 3 below 2.
Rn-222	Radon-222, the gas from uranium-238 decaying via radium in soil and rock.

SPECIES

4(d) rule	An ESA rule tailoring protections for a threatened species, relaxing or extending take limits.
Critical habitat	Ground mapped by rule as essential to a species' recovery; the polygons on the plates.
E / T	Status beside each name: E Endangered, T Threatened under the ESA.
ECOS	USFWS Environmental Conservation Online System, the listed-species record and county list.
ECOS code	ECOS species identifier, a letter and three characters (E071); the key to its page at ecos.fws.gov.
Federal nexus	Federal funding, permit or action that brings Section 7 consultation into a project.
IPaC	USFWS Information for Planning and Consultation, the online species and habitat query tool.
Section 7	ESA consultation: federal agencies consult USFWS so their actions do not jeopardise a species.
Section 9	ESA prohibition on take of listed animals anywhere; plants on federal land.
Take	Harass, harm, hunt, wound, kill, trap or collect; harm includes habitat change that injures.
USFWS	US Fish and Wildlife Service.

WETLANDS

Cowardin	USFWS 1979 wetland classification: five systems and the code grammar below.
DEP	Florida Department of Environmental Protection, issuer of the ERP.
ERP	Environmental Resource Permit, Florida's state dredge, fill and stormwater permit.
ESHA	Environmentally Sensitive Habitat Area, a California Coastal Act designation; buffers often 100 ft.
JD	Jurisdictional determination: the Corps' finding, approved or preliminary, that a wetland is a water of the US.
NWI	USFWS National Wetlands Inventory, mapped from imagery.
NWI code	Read left to right: system letter, subsystem digit, class letters, subclass digit, water regime letter, lower-case modifier (R4SBC: riverine, intermittent, streambed, seasonally flooded).
└ M	Marine system: open ocean and its exposed coastline.
└ E	Estuarine system: tidal, salt to brackish; bays, salt marsh, flats.

Codes key *continued*

WETLANDS continued

└ R	Riverine system: water within a channel; rivers and creeks.
└ L	Lacustrine system: lakes, reservoirs, ponds over 20 acres.
└ P	Palustrine system: freshwater marsh, swamp, bog, small pond.
└ E1	Subsystem: subtidal.
└ R2	Subsystem: lower perennial.
└ UB	Class: unconsolidated bottom, open water over mud, sand or gravel.
└ SB	Class: streambed, a channel dry part of the year.
└ FO	Class: forested, trees over 6 m tall.
└ SS	Class: scrub-shrub, woody plants under 6 m.
└ EM	Class: emergent, rooted herbaceous plants standing in water.
└ AB	Class: aquatic bed, plants on or below the water surface.
└ US	Class: unconsolidated shore; beach, bar or flat.
└ C	Water regime: seasonally flooded.
└ EM1	Subclass: persistent.
└ F	Water regime: semipermanently flooded.
└ H	Water regime: permanently flooded.
└ x	Modifier: excavated.
NWP	Nationwide permit: a general Section 404 permit for small fills (NWP 29: residential, under 0.5 acre).
Section 404	CWA permit for dredged or fill material in a jurisdictional wetland or stream, issued by USACE.
USACE	US Army Corps of Engineers, the Section 404 permitting authority.

PIPELINES

CO2	Carbon dioxide, piped for injection or industry; a commodity class on the pipeline key.
DOT	US Department of Transportation, PHMSA's parent department.
EIA	US Energy Information Administration, publisher of the generalised public pipeline geometry.
NPMS	National Pipeline Mapping System (PHMSA): precise alignments, released under access rules.
PHMSA	Pipeline and Hazardous Materials Safety Administration, the federal pipeline regulator (US DOT).

COMMUNITY

AFFF	Aqueous film-forming foam, the PFAS-bearing firefighting foam used at airports and bases.
BTS	Bureau of Transportation Statistics, publisher of the NTAD.
FAA	Federal Aviation Administration, the airport and heliport register.
NCED	National Conservation Easement Database.
NPS	National Park Service, keeper of the National Register of Historic Places.
NRHP	National Register of Historic Places.
NTAD	National Transportation Atlas Database: the BTS compilation of FAA airports and heliports.
OSM	OpenStreetMap, the volunteer world map queried for schools, clinics and hospitals.
Overpass	The query service for OpenStreetMap, queried live within 1 mi.
PAD-US	USGS Protected Areas Database of the United States.
PFAS	Per- and polyfluoroalkyl substances, persistent industrial chemicals ("forever chemicals").
Receptor	A person, place or resource contamination could reach; schools, daycares and clinics are sensitive receptors.
Section 106	NHPA review federal agencies run before permitting or funding work near a listed historic property.

AIR QUALITY

98th percentile	The daily value 98 percent of a year's days fall at or under; the PM2.5 daily test.
AirNow	EPA's hourly real-time feed, uncertified; the AQI at the time of this report.
AQI	Air Quality Index, EPA's 0 to 500 scale; six bands, Good to Hazardous.

Codes key *continued*

AIR QUALITY continued

AQS	EPA Air Quality System, the archive of certified monitor readings behind the almanac.
Design value	Three-year average of a monitor's readings, the figure tested against a standard.
Exceedance	A day over AQI 100 (Unhealthy for Sensitive Groups and above); a count, not a violation.
ICAO id	Four-letter International Civil Aviation Organization station identifier (K plus three letters in the lower 48).
KTPA	ICAO station id of Tampa International Airport, the weather station whose wind record drew the rose, 1991 to 2020.
NAAQS	National Ambient Air Quality Standards, 40 CFR 50: PM2.5 9.0 annual and 35 daily µg/m³; ozone 70 ppb.
O3	Ozone, a ground-level pollutant; AQS parameter 44201.
PM10	Coarse particles under 10 micrometres, in µg/m³.
PM2.5	Fine particles under 2.5 micrometres, in µg/m³; AQS parameter 88101.
ppb	Parts per billion of air, the ozone unit.
µg/m³	Micrograms per cubic metre of air, the particle unit.

WIND AND STORMS

EF scale	Enhanced Fujita tornado damage scale: EF0 65 to 85 mph, EF1 86 to 110, EF2 111 to 135, EF3 136 to 165, EF4 166 to 200, EF5 over 200; F0 to F5 is the older Fujita scale, used before February 2007.
HURDAT2	NOAA National Hurricane Center best-track database: each Atlantic (1851 on) and northeast Pacific (1949 on) cyclone's centre, wind and status at six-hour steps.
NHC	National Hurricane Center, the NOAA office that forecasts tropical cyclones and keeps HURDAT2.
NRI	FEMA National Risk Index: a census-tract rating for 18 natural hazards (Very Low to Very High) from expected annual loss, social vulnerability and community resilience.
OIR-B1-1802	Florida's uniform wind mitigation inspection form (Office of Insurance Regulation), valid five years; each feature it records earns a premium discount under s. 627.0629.
Saffir-Simpson	Hurricane categories by one-minute sustained wind: 1 is 74 to 95 mph, 2 is 96 to 110, 3 is 111 to 129, 4 is 130 to 156, 5 is 157 or more.
SPC	NOAA Storm Prediction Center; its tornado database runs from 1950 with a start and an end point for each tornado.

MAP AND DATA TERMS

ArcGIS	Esri's map server software; FeatureServer and MapServer are its layer endpoints.
CAS	Chemical Abstracts Service registry number: one identifier per substance, worldwide.
Checks	Passed, passed with gaps, or failed: a retrieval and consistency check of the sources and figures, not a verification of the public records; the methodology page sets out each.
CID	PubChem compound identifier, the record number behind each chemical link.
Composite	The weighted sum of the sixteen section scores, 0 to 10; the rating word comes from its band.
EPSG	Coordinate system registry id; EPSG:3857 is Web Mercator (the maps), EPSG:4326 plain latitude and longitude.
IARC	International Agency for Research on Cancer, whose carcinogen classes chemical descriptions cite.
Ladder	Five ticks filled to the level's step: Low 1, Moderate 2, Elevated 3, High 4, Severe 5.
Mapbox	The map service behind the satellite imagery and, where the Census geocoder failed, the geocode.
NOAA	National Oceanic and Atmospheric Administration: coastal, storm-surge and weather records.
Not assessed	The section's source did not return; no score and no weight in the composite.
PubChem	The National Institutes of Health open chemistry database; chemical descriptions and structures.
TIGER	Census Bureau address and street line file, the geocoder's reference.
TRI N-code	TRI category code for related compounds reported together (N420 lead compounds).
WGS 84	World Geodetic System 1984, the GPS latitude and longitude datum used throughout.

Provenance: report PLM-20261014151531 · schema prelim-report/0.1 · generated October 14, 2026 (PDT) · 177 codes · 24 shared with report.json